

4-032099

10-10

API Number: 15-163-01652-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE NE NW /4 SEC. 14, 09S, 19 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# ~~2914~~ 3194 KC

Lease: Landry Well # 3

Operator: Tri United, Inc.

County: Rooks

Address: 950 270th Avenue  
Hays, Kansas 67601

Well total depth 3480 113, 10 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1478 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 10 Month: October Year: 1995

Plugging proposal received from: Manny

Company: Mike's Testing & Salvage Phone:

Were: Order 285 sxs 60/40 pozmix - 10% gel - 300# hulls.  
Allied Cement Company.  
Order sand and common cement.

RECEIVED  
STATE CORPORATION COMMISSION

OGT 20 1995  
10-20-95

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]  
CONSERVATION DIVISION  
Wichita, Kansas

Completed: Hour: 4:20 P.M., Day: 10, Month: October, Year: 1995

Actual plugging report: 8 5/8" set at 1478' cwc. w/800 sxs. 5 1/2" set at 3478' with 200 sxs. K.C. Perf's 3240' - 3244'. CIBP at 3260' Arb. Sanded back to 3190' with 5 sxs common cement on sand with bailer. One shot recovered 2150'+ casing. Mixed and pumped down casing 165 sxs cement blend with 300# hulls from 2150' circulated fluid to surface. Pulled to 800'. Mixed and pumped down casing 30 sxs cement blend circulated fluid to surface. Pulled casing to 250' circulated cement to surface with 55 sxs cement blend. Pulled casing. Hole full of cement. Plug complete.

Remarks: Witnessed by Dennis Hamel.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED  
DATE 10-27-95  
INV. NO. 43887