

6 031398

3462

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-143-01651-00-00

NW SE NW, SEC. 14, T 9 S, R 19 W/E^{xx}
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Phillips Pet. Co.
Operator: Phillips Pet. Co.
Name & Address: Route #3 Box 20 A
Great Bend Ks. 67530

Lease Name Landry Well # 2
County Rooks 113.07
Well Total Depth 3479 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1464

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address

Company to plug at: Hour: Day: 25 Month: July Year: 1990

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8 set at 1464 w/800 sks. 5 1/2 set at 3477 w/200 sks. O.H.

3477-79. Order sand and common cement. 1 Pull pipe. Order 225 sks 65/35 poz 8% gel

500 lbs. hulls. Allied Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:30A Day: 25 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3425 w/5 sks common cement on

sand w/bailer. Recovered 2300 of 5 1/2 casing. Sq 8 5/8 w/225 sks cement blend w500 lbs.

hulls mixed in to max psi 700 lbs. Close in psi 400 lbs.

STATE CORPORATION COMMISSION

AUG - 7 1990

8-7-90

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

AUG 15 1990

DATE:

INV. NO. 28931

7-25

SEP 14 1990

Signed Carl Goodrow
(TECHNICIAN)

Gilbert Balthazor