

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01647-00-00
Spot: CNESESW Sec/Twnshp/Rge: 14-9S-19W
990 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: KABA Well Number: 4
County: ROOKS Total Vertical Depth: 3504 feet

Operator License No.: 31824
Op Name: BROWN, THOMAS M.
Address: 403 NW 3RD PO BOX 250
PLAINVILLE, KS 67663

Production Casing Size: 5.5 feet: 3479 200 SX CMT 113.88
Surface Casing Size: 8.625 feet: 1486 900 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2003 9:00 AM
Plug Co. License No.: 31824 Plug Co. Name: BROWN, THOMAS M.
Proposal Rcvd. from: THOMAS M. BROWN Company: BROWN, THOMAS M. Phone: (785) 434-7141

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 600# hulls - 25 sxs gel.
WLM 3500'.
Hole in casing at 1750' and 1200'+.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/03/2003 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementer to 5 1/2" casing.
Squeezed 50 sxs cement with 400# hulls, followed with 20 sxs gel, followed with 150 sxs cement.
Opened annulus 5 1/2" - 8 5/8" S.P.
Circulated at 30 - 35 bbls of water to pit with cement - circulated to surface.
Used additional 200 sxs cement.

RECEIVED
2-12-03
FEB 12 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 2-13-03

INV. NO. 2003061191

FEB 10 2003