

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19309-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 35-25S-8E
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LADD B Well #: 3
County: GREENWOOD Total Vertical Depth: 2484 feet

Operator License No.: 5697
Op Name: JACKSON BROS., L.L.C.
Address: 116 EAST THIRD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2518	717	
SURF	8.625	102		

\$ 80.73

Well Type: EOR UIC Docket No: E05052.1 Date/Time to Plug: 02/09/2007 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: 50' cement plug @ 2479' 50' cement plug @ 715' 301' to surface.

RECEIVED
APR 02 2007
KCC WICHITA

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2007 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

mixed & dumped 14 sxs cement with dump baler @ 2479', shot casing @ 717' pumped 30 sxs. Cement, pulled casing to 301' pumped 120 sxs. Cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DISTRICT #3

MAR 26 2007

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
2471	2478		

INVOICED
DATE 4-5-07
INV. NO. 2007061549

Remarks:

Plugged through: CSG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

PVT