

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21712-00-00
Spot: SENWSW Sec/Twnshp/Rge: 33-26S-13W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: LEMON Well #: 4
County: PRATT Total Vertical Depth: 4537 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4085		\$ 147.45
CIBP		4340		
PROD	5.5	4535	3039	WITH 250 SX CMT
SURF	10.75	321		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: AL BALMARO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3700' & 5 SX CMT. PLUG AT 850' WITH 15 SX GEL & 50 SX CMT. PLUG AT 350' WITH 80 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2007 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
SAND BACK TO 3700' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. SPOT PLUGS THROUGH CASING & TUBING. 1ST PLUG AT 850' WITH 15 SX GEL & 50 SX CMT. NO RETURNS. 2ND PLUG AT 350' WITH 80 SX CMT. NO RETURNS. SHUT DOWN OVERNIGHT TO LET CMT SET. 3/27/07: TAG TOC @ 480'. RUN 2 3/8" TUBING INTO 350' SPOTTED 80 SX CMT WITH 3% CC WITH 250# HULLS OF HULLS MIXED IN WITH CMT. BROKE CIRCULATION, BUT FLUID FALLING BACK. PULLED TUBING OUT OF HOLE. LET CMT SET FOR 2 HOURS. RUN IN & TAG TOC @ 390'. RUN TUBING BACK IN TO 350' & SPOT 80 SX CMT WITH 3% CC. HAD RETURNS. 3RD PLUG AT 60' WITH 40 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4509	4513		
4350	4360		
4222	4232		
3826	3836		

INVOICED
DATE 4-5-07
INV. NO. 2007061553
RECEIVED
APR 02 2007
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.
Plugged through: TBG

District: 01 Signed Stephen J. Pfeifer (TECHNICIAN)
RECEIVED
MAR 28 2007
KCC Dodge City