

To: ⁶ 030917
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,924 -00-06
100' N
SE NE NW, SEC. 28, T. 9 S, R. 19 W/E
4390 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804
Operator: Dreiling Ltd. of Colorado
Name & Address 410 17th St. Ste 1140
Denver, Colorado 80202

Lease Name Kuehnl Well # 2
County Rooks 120.25
Well Total Depth 3700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 207'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____
Address Hays, Kansas

Company to plug at: Hour: PM Day: 27 Month: 7 Year: 19 87

Plugging proposal received from Dave Dreiling
(company name) Dreiling Ltd. (phone) _____

were: 8 5/8 set @ 207' w/150 sx. 4 1/2 set @ 3699' w/ 200 sx to Perf. 3320'
order, sand and com. cmt., plug bottom, shoot and pull pipe.
order 200 sx. econolite 65/35 poz 10% gel 2% dicel, 6 sx hulls
Halliburton Cmt. Co.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 2:55 PM Day: 27 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Bottom sanded to 3270' w/4 sx cmt. on sand
w/ bailer. one shot recovered 2750' of 4 1/2" csg.
Squeezed 8 5/8' csg w/ 200 sx cement blend and 6 sx hulls
Added in. Max. PSI 400 Close in PSI 300 Plug complete

8/18/87
AUG 18 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-18-87
INV. NO. 17856

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow