

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21680-00-00
Spot: NWNENW **Sec/Twnshp/Rge:** 28-9S-19W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: KUEHNL **Well Number:** 3
County: ROOKS **Total Vertical Depth:** 1569 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet: 150.99
Surface Casing: Size 8.625 feet: 216 145 SX CMT
Production: Size 4.5 feet: 1569 380 SX CMT
Liner: Size feet:

Well Type: SWD **UIC Docket No:** D21211.0 **Date/Time to Plug:** 12/16/2002 9:00 AM

Plug Co. License No.: 6901 **Plug Co. Name:** D S & W WELL SERVICING, INC.

Proposal Rcvd. from: EDWARD S. NEMNICH **Company:** D S & W WELL SERVICING, INC. **Phone:** (620) 587-3361

Proposed Plugging Method: Ordered out 135 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cedar Hills SWD. Fluid level 800'. PBTB 1569'. Perfs 1230' - 1270'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/16/2002 10:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 75 sxs 60/40 pozmix - 10% gel and 400# hulls down 4 1/2" casing.
Max. P.S.I. 1000#. S.I.P. 800#.
Hooked up to backside and pumped 10 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 400#.

RECEIVED
1/3/03
JAN 03 2003

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100.

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

1-3-03

INV. NO.

2003061023

DEC 30 2002

DREILING LTD. OF COLORADO
 410 - 17TH ST., #1140

#3 KUEHNL

28-9-19W
 NW NE NW

DENVER, CO 80202

CONTR C & R DRLG.

CTY ROOKS

GEOL

FIELD ZURICH TWST WEST

E 2175 KB CM 6/16/82 CARD ISSUED

8/5/82

IP SWDW

GED HILLS 1230-1270

+	+	+	+
+	+	+	+
+	+	+	+

API 15-163-21,680

LOG	TOPS	DEPTH	DATUM
SC		1655	+ 520
TOP		3125	- 950
HEEB		3328	-1153
TOR		3352	-1177
LANS		3368	-1193
B KC		3587	-1412
ARB		3630	-1455
TD		3630	-1455

8-5/8" 216/145sx, 4 1/2" 1569/380sx

DST (1) 3364-3414/30-60-30-30, 70'
 SO SPKD WM, SIP 555-496#, FP 25-33/
 42-52#

DST (2) 3432-68/30-60-30-60, 70'

WCM, PRESS NA

DST (3) 3632-45/30-60-30-60, 40'

OSM, SIP 42-33#, FP 13-13#

MICT - CO, PF (GED HILLS) 1230-70,
 INJECTION RATE SATISFACTORY, SWDW

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS