

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21326-00-00
Spot: CNENENW Sec/Twnshp/Rge: 28-9S-19W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: KUEHNL Well Number: 1
County: ROOKS Total Vertical Depth: 3705 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet: \$120.41
Surface Casing: Size 8.625 feet: 248 190 SX CMT
Production: Size 4.5 feet: 3703 475 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/16/2002 8:30 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
PBTD 3610' - CIBP.
Perfs 3368'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/16/2002 9:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 200 sxs 60/40 pozmix - 10% gel with 400# hulls down 4 1/2" casing.
Max. P.S.I. 500#. S.I.P. 400#.
Hooked up to backside and pumped 25 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 400#.

12/20/02

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12-23-02

W.C. NO. 2003060969

Form CP-2/3

DEC 17 2002

DREILING LTD OF COLORADO
 410 17TH #1140 DENVER, CO 80202 #1 KUEHNL 28-9-19W NE NE NW
 CONTR C&R DRILLING CO CTY. ROOKS
 GEOL FLOYD H. HOFFMAN FIELD ZURICH TWST EXT (1/8 W)

E 2187 KB CM 8/9/81 CARD ISSUED 11/5/81 IP P 60 BOPD & NW
 LANS 3368-3373

+	+	+
+	+	+
+	+	+

API 15-163-21,326

LOG	TOPS	DEPTH	DATUM
ANH		1554	+ 633
TOP		3126	- 939
HEEB		3329	-1142
TOR		3357	-1164
LANS		3367	-1180
B KC		3586	-1399
ERO ARB		3609	-1422
ARB		3618	-1431
TD		3705	-1518

8 5/8" 248/190sx; 4 1/2" 3703/475sx
 DST (1) 3613-3638/TIMES NA, REC 60' GF
 180' OCM & MCO, SIP 776#, FP 66-109#
 DST (2) 3637-3653/TIMES NA, REC 100'
 MO, 30' HOCM, SIP 701#, FP 33-67#
 DST (3) 3653-3670/TIMES NA, REC 25' M
 SIP 721-694#, FP 42-63/42-63#
 DST (4) 3670-3690/TIMES NA, REC
 690' MCW, SIP 1258-1049#, FP 63-211/232-358#
 MICT - CO, PF 24/3622-3628, AC500G,
 SWB, SET PLUG OVER PFS 3622-3628,
 PF 20/3368-3373, AC2000G, SWB LD,
 R&T, POP, P 60 BOPD, NW 9/20/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS