

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22486-00-00
Spot: CSENWNW Sec/Twnshp/Rge: 9-9S-20W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: WHISMAN Well Number: 1
County: ROOKS Total Vertical Depth: 3762 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 243
Production: Size 5.5 feet: 3759
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/03/2002 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 350 sxs cement and 500# hulls.
Perforate at 700' - 1750' - 2200'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/03/2002 4:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 243' w/150 sxs cement. 5 1/2" casing at 3759' w/575 sxs cement.
Bridge at 1690' - pumped 54 bbls into casing at 600#.
RIH with 2 7/8" tubing to 2295'. Circulated with 85 sxs cement and 300# hulls.
Pulled tubing to 1147' and pumped 110 sxs with 200# hulls to circulate.
Pulled all tubing and squeezed 150 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Tied to 8 5/8" x 5 1/2" annulus and squeezed 5 sxs to 500#.

RECEIVED
JUN 21 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. HOXIE TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger R. Moses
(TECHNICIAN)

SOUTHWEST ENERGY
DEVELOPMENT CORPORATION

BOX 3744
HOUSTON, TX 77253


#1 WHISMAN

9-9-20W
SE NW NW

CONTR WOODMAN-IANNITTI DRILLING CITY ROOKS

GEOLOGIST DON E. MOORE

FIELD WHISMAN



ELV 2220 KB SPD 10/13/84 CARD ISSUED 2/21/85 IP P 25 BO & 2 BWPD
2216 GL
API 15-163-22,486 ARB 3731-3754

DRLRS	Tops	Depth/Datum
ANH		1719+ 501
TOP		3198- 978
HEEB		3403-1183
LANS		3441-1221
BKC		3658-1439
CONG		3708-1488
ARB		3716-1496
RTD		3760-1540
LTD		3762-1542

8 5/8 " 243 / 150SX, 5 1/2 " 3759 / 575SX
 DST (1) 3504-3619 (LKC) / 45-60-45-60, 1600' TF, 120' OCWM (10% G, 5% OIL, 70% W, 15% M), 240' SOCSW (2% OIL, 95% W, 3% M), 1240' SW, SIP 1047-1047#, FP 100-491 / 558-735#, HP 1825-1825#
 DST (2) 3698-3725 (PENN, ARB) / 30-30-30-30, REC 5' DM, SIP 67056#, FP 45-45 / 45-45#, HP 1960-1960#
 DST (3) 3698-3745 (PENN, ARB) / 45-60-30-60, REC 55' DM, W / FEW SPKS OIL (2% OIL, 98% M), SIP 491-368#, FP 33-33 / 44-44#, HP 1982-1982#
 DST (4) 3698-3760 (PENN, ARB) / TIMES NA, REC 300' DM, PKR FAILURE, MISRUN
 DST (5) 3694-3760 (PENN, ARB) / 45-60-45-60, REC 50' SOCDM (20' -35% OIL, 10% W, 55% M, 30' -10% OIL, 2% W, 88% M), SIP 624-469#, FP 33-45 / 45-45#, HP 1993-1993#
 MICT -CO, PF (ARB) 3746-54, W / 3-SPF, AC 1000G (15% HCL), SWB DWN, SO, PF (ARB) 3737.5-3745.5, W / 3 SPF, AC 1000G (15% HCL), SWB DWN, SO, PF (ARB) 3731-34, W / 3 SPF, AC 500G (15% HCL), SWB DWN, SO, SET 2 3/8 " TBG AT 3734, POP, P 25 BO & 2 BWPD

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

SOUTHWEST ENERGY