

6 070841

5-14

API NUMBER 15-

163-23,075-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE, SEC. 34, T 9 S, R 19 W/EX

990 feet from S section line

²¹¹⁰
~~2310~~ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30259

Lease Name Webster Well # 7

Operator: Werth Exploration Trust

County Rooks 121.39

Name & Address Box 533

Well Total Depth 3735 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

C/O Andy Werth

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Lloyd Drilling Co. License Number 3300

Address St. Peter Box 59 Morland, Ks. 67650

Company to plug at: Hour: PM Day: 14 Month: May Year: 19 90

Plugging proposal received from Mike Deenihan

(company name) Lloyds Drilling Co. (phone)

were: 8 5/8 - 253' s.p. cwc w/140 sks 60/40 poz 3% gel 2% cc. By Allied.

Arb well 3708. Elv. 2174. Anhy 1553. No cir problems. Mud condition 53 vis - 9.9 weight.

Proposal 225 sks 60/4 poz 6% gel 3% cc and 8 5/8 plug. Spot with drill stem, circ heavy mud between all plugs 25 sks at 3640 - 25 sks at 1560 - 100 sks w/1 f.c. at 920 - 40 sks at 300 ft. - 10 sks w.p. at 40'. 15 sks rathole 10 sks mousehole cir.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 7:35PM Day: 14 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Lloyd Drilling ordered 225 sks 60/40 poz

6% gel 3% cc and 8 5/8" plug and 1 sk f.c. Spotted with drill stem, circ hole, heavy mud between all plugs.

1st plug at 3640' w/25 sks cement 4th plug at 300' w/40 sks cement

2nd plug at 1560' w/25 sks cement. 5th plug at 40' w/plug and 10 sks cement

3rd plug at 920' w/100 sks cement w/1 sk f.c. 10 sks mousehole cir.

Remarks: Cemented by Allied Cement Great Bend, Ks.

(If additional description is necessary, use BACK of this form.)

INVOICED Reserve this plugging.

DATE 6-6-90 5-21-90

INV. NO. 28351

Signed Marion J. Schmidt (TECHNICIAN)