

12-30 15-163-02859-00-01

6 041000

API NUMBER 15-

7-9-59

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NW SE, SEC. 34, T 9 S, R 19 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8133

Lease Name Webster Well # 1

Operator: William E. Hammerschmidt

County Rooks 120.61

Name & Address 904 S. Sec LOne

Well Total Depth 3711 feet

Plainville, Ks. 67663

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 197' w/150 s

Abandoned Oil Well Gas Well But Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: 9:00 Day: Dec Month: Dec Year: 19 88

Plugging proposal received from Bill Hammerschmidt

(company name) Same (phone)

were: 4 1/2" casing set at 3707' w/NA sks. Top perf at 3443'. Ran wireline to 2500'.

PBTD 3648'; Sq at 750' circ w/200 sks (1979). Holes in casing at 1110', 1430' 1960'.

Ordered 200 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15 PM Day: 30 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 200 sks cement w/1/4# F.C. plus 5 sks

Hulls, mixed in cement. Max 600# S.I. 300# psi. Pumped in 8 5/8" casing 0 sks cement.

Max 1000# S.I. 800 psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-19-89

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 23703

Dennis L. Hamel