

4-031758

9-22

152R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,139-00-00
150'E.of
NW SW SW /4 SEC. 33, 09 S, 19 W
4800 feet from S section line
900 feet from E section line

Operator license# 5140

Lease Hamel A well # 2

Operator: Frontier Oil

County Rooks

121.94

Address: 1720 K.S.B. & T. Building
Wichita, Kansas 67202

Well total depth 3752 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 220 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 22 Month: September Year: 92

Plugging proposal received from: Dick Parker

Company: Frontier Oil Phone: _____

Were: Order 275 sx. 65/35 pozmix - 10% gel. - 500# hulls.
D.V. tool @ 1649'.
Hole open by wireline.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 10:00A.M., Day: 22, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 220' w/150 sx. cwc. 5 1/2" set @ 3741' w/150 sx. D.V. tool set @ 1649' w/350 sx. cwc. O.H. ar buckle 3740' - 3752'. Squeezed 5 1/2" w/275 sx. cement blend w/500# hulls mixed in to Max. P.S.I. 1200#. Close in P.S.I. 1000#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

9-24-92
SEP 24 1992

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING _____, CASING . Elevation: _____
Wichita, Kansas

I did and did not observe the plugging.

Carl Goodrow

DATE 10-6-92

(agent)

INV. NO. 3632a

Form CP-2/3