

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03262-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 5-16S-12W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: STANDINGER A Well #: 2  
County: BARTON Total Vertical Depth: 3260 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3242	0	w/unknown sxs cmt
SURF	8.625	522	0	w/225 sxs cmt <b>#105.95</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2007 10:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2007 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 2863' - pumped 50 sxs cement with 200# hulls.  
Pulled tubing to 1628' - pumped 100 sxs cement with 200# hulls - circulated cement.  
Tied onto 5 1/2" - pumped 120 sxs cement - circulated cement out the backside - shut in backside full.  
Tied back on to 5 1/2" and squeezed with 130 sxs cement with 100# hulls.  
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
2995	3029		
2834	2845		

**INVOICED**  
DATE 4-10-07  
INV. NO. 2007061557

Remarks: LEASE ALSO KNOWN AS NW BEAVER UNIT #9-2. ALLIED CEMENTING COMPANY-TICKET #30147.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

CONSERVATION DIVISION  
WICHITA, KS

APR 02 2007

*RET*

PHIL HAN OIL ET AL

#2

STANDIGER A

5-16-12W  
NW NW SW

Contr.

BARTON

County

E 1827

Comm. 8-2-48

Comp. 10-29-48

IP 334 BOPD @ 12% WTR.

PHY POT

Tops	Depth	Datum
ANH	770	
HEEB	2894	
LANS	2991	
QTZ	3240	
T.O.	3258	

Casing

8" 300  
5" 3242

R/A LOG  
1800' OIH  
SWB 4 BOPH, 4 HRS  
PB 3200: PERF 24 S, 3167-  
71: PB 3100: PERF 36 S,  
3068-76: PB 3054:  
PERF 36 S, 3018-29  
ACID 3000

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

