

889 K cap

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21-~~828~~ 0000  
C-N 1/2- SW, Sec. 33, T 9 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

Operator License # 5399

Lease Name CASEY Well # 1

Operator: AMERICAN ENERGIES CORP. County ROCKS.

Name & Address 575 FOURTH FINANCIAL BLDG. Well Total Depth 200 feet

WICHITA, KANS. 67202 Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 4 1/2 feet 60

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated ON WRONG LOCATION - MOVED RIG.

Plugging Contractor J.W. DRILLING License Number 394

Address 200 EAST 1<sup>ST</sup> #500 WICHITA, KANS. 67202

Company to plug at: Hour: 2:00 PM Day: 15<sup>th</sup> Month: OCT. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO BILL ROACH.

(company name) J.W. DRILLING (phone) 316-278-2367

were: RIG WAS ON WRONG SPOT LOCATION - DID NOT HAVE SURFACE PIPE CEMENTED IN. I INFORMED HIM TO SET PIPE 5 1/2" OR MORE TO A DEPTH OF 50' BELOW ANY FRESH WATER WITHIN A MILE RADII. THEY SPOTTED 20' CMT @ 180' PUT IN 60' OF 4 1/2" CSG. CIRCULATED TO SURFACE w/ 65' CMT. 10' IN RHT HOLE.

Signed Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:00 PM Day: 15<sup>th</sup> Month: OCT. Year: 1982

ACTUAL PLUGGING REPORT T.O - 200' EL No S.P.

ORDERED 95' 50/50 Pozmix 6% GEL - 3% CA-CL.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 180' EL w/ 20' CMT.

PUT IN HOLE 60' OF 4 1/2" CSG. FOR S.P.

CIRCULATED CMT TO SURFACE w/ 65' CMT. (10' IN RHT HOLE) (CIRCULATE)

Remarks: CEMENTED BY SWD CMT.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1982  
10-26-82  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as stated and that I (did did not) observe this plugging.

Signed Marion Schmidt  
(TECHNICIAN)

INVOICED  
11-9-82  
1519-W(2)