

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22071-00-00
Spot: NWNSWSE Sec/Twnshp/Rge: 14-27S-10W
1090 feet from S Section Line, 1880 feet from E Section Line
Lease Name: DYKE BICK Well #: 1-14
County: KINGMAN Total Vertical Depth: 4410 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 4109 IRONWOOD
WICHITA, KS 67226

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 285

\$ 143.33

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/08/2007 5:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 35 sxs @ 1500'; 35 sxs @ 1000'; 35 sxs @ 335'; 25 sxs @ 60'; 15 sxs in rathole; and 10 sxs in mousehole.

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 01/09/2007 7:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Ran open end drill pipe to 1500' and spotted 35 sacks of cement. Pulled drill pipe to 1000' and spotted 35 sacks of cement. Pulled drill pipe to 335' and spotted 35 sacks of cement. Pulled drill pipe to 60' and circulated cement to surface. Circulated 15 sacks of cement in rathole and 10 sacks of cement in mousehole.

60/40 posmix with 4% gel

Allied

Perfs:

RECEIVED
KCC DISTRICT #2
JAN 24 2007
WICHITA, KS


INVOICED
DATE 4-10-07
INV. NO. 2007061567

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 04 2007

CONSERVATION DIVISION
WICHITA, KS

