

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20473-00-01
Spot: SENENE Sec/Twnshp/Rge: 13-19S-2E
4302 feet from S Section Line, 420 feet from E Section Line
Lease Name: REMPER Well #: 2
County: MARION Total Vertical Depth: 2890 feet

Operator License No.: 30483
Op Name: KREMEIER, LES DBA KREMEIER PROD
Address: 3183 US HIGHWAY 56
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2890		
SURF	8.625	206		

\$ 93.93

Well Type: SWD UIC Docket No: D23631.0 Date/Time to Plug: 03/19/2007 9:00 AM
Plug Co. License No.: 33307 Plug Co. Name: FLINT HILLS OIL CO., LLC
Proposal Rcvd. from: LES KREMEIER Company: FLINT HILLS OIL CO., LLC Phone: (785) 258-2544

Proposed Plugging Method: Per K.C.C. Rules & Regulations.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2007 10:15 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

3/19/2007 - Packer stuck in 5 1/2" casing. Ran wireline & tagged top of packer @ 1,961'. Sat C.I.B.P. @ 1,959'. Perforated 5 1/2" casing from 1,951' to 1,957' with 24 shots. Ran 2 3/8" tubing to 1,945' & spotted 50 sxs. cement w/4% calcium chloride. Pulled tubing. Ran bond log from 300' to surface. 5 1/2" casing had cement on backside. Ran tubing to 280' & circulated 35 sxs. cement to surface. Cut off wellhead & confirmed cement at 0' on backside of 5 1/2" casing. 03/21/2007 - Checked top plug. Cement down 90' - informed operator to top off plug. 3/28/2007 - Ran tubing to 87' & filled 5 1/2" casing to surface 35 sxs. cement. 3/29/2007 - Checked top plug & cement at 0'.

INVOICED
DATE 4-10-07
INV. NO. 2007061560

Remarks: USEB 60/ 40 POSMIX W/4% GEL BY CONSOLIDATED. INVOICE # 17007 & # 17032.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 04 2007

CONSERVATION DIVISION
WICHITA, KS