

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22492-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 29-34S-3W
1550 feet from S Section Line, 2000 feet from E Section Line
Lease Name: KLEINSORGE Well #: 1
County: SUMNER Total Vertical Depth: 3447 feet

Operator License No.: 31885

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	263		

Op Name: M & M EXPLORATION, INC.

Address: 60 GARDEN CENTER, STE. 102
BROOMFIELD, CO 80020

\$ 112.03

Well Type: CB LH Pkt

UIC Docket No:

Date/Time to Plug: 01/04/2007 4:30 PM

Plug Co. License No.: 33843

Plug Co. Name: TERRA DRILLING, LLC

Proposal Rcvd. from: EVERETT LLOYD

Company: TERRA DRILLING, LLC

Phone: (620) 388-3675

Proposed Plugging Method: THE HOLE BECAME DEVIATED TO 4% @3447'. PULLED DRL. PIPE TO SPOT CMT. AT 3284'. SPOT 175 SKS. PULLED 5 STAINS. DRL PIPE STUCK IN HOLE. BACK OFF DRILL PIPE @2550'. PLUGGED HOLE WITH 35 SKS @1250', 35 SKS @ 700', 25 SKS @ 60'. 15 SKS IN RAT HOLE AND 120 SKS IN MOUSE HOLE.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 02/04/2007 9:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

CROOKED HOLE @ 3447' (4 DEGREES). PULLED DRILL PIPE OUT OF HOLE AND REMOVE BIT. TRIP BACK IN HOLE TO A DEPTH OF 3284'. DRILL PIPE STOPPED. SPOTTED 175 SKS CMT.. PULLED 5 STANDS OF DRILL PIPE WAIT ON CMT TO SET. COULD NOT MOVE DRILL PIPE. BACKED OFF DRILL PIPE @ 2550' AND LEFT PIPE IN HOLE. SPOTTED 35 SKS @1250. PULLED DRILL PIPE TO 700' SPOTTED 35 SKS. PULLED DRILL PIPE TO 300' SPOTTED 35 SKS CMT. PULLED DRILL PIPE TO 60 ' SPOTTED 25 SKS CMT.. CIR. 15 SKS IN RAT HOLE AND CIR. 10 SKS IN MOUSE HOLE.

INVOICED


DATE 4-10-07
INV. NO. 2007061561

Remarks: ALLIED CEMENTING CO. 60/40 POSMIX 4% GEL TICKET #32409

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

CONSERVATION DIVISION
WICHITA, KS



Pkt