

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00621-00-00
Spot: SESESE Sec/Twnshp/Rge: 22-30S-8W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEST SPIVEY UNIT Well #: 39-1
County: KINGMAN Total Vertical Depth: 4375 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4374		150 SX
SURF	8.625	206		250 SX

\$ 142.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2007 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PERFS 4284'-4304'. SAND BACK ABOVE PERFS 50' CAP WITH 5 SKS CMT. @ 1250' 35 SKS., @ 750 35 SKS. CIRC @ 250'- TO 0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/09/2007 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

NO STRETCH ON CASING, PRESSURED UP TO 300#, HELD OK PERFED @250', INJ RATE 4BBL @ 700#. PUMPED 35 SKS 3% CACL, BALANCED PLUG @1250' WAITED 1.5 HRS. PERFED @750' INJ RATE 3.5 BBL @ 750#, PUMPED 35SKS 3% CACL, BALANCED PLUG @ 750, WAITED 1 HR PERF @ 250' CIRC CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4284	4304		

INVOICED


DATE 4-10-07
INV. NO. 2007061562

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

CONSERVATION DIVISION
WICHITA, KS
WICHITA, KS

