

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01191-00-00
Spot: NWSESE Sec/Twnshp/Rge: 23-30S-8W
1040 feet from S Section Line, 990 feet from E Section Line
Lease Name: WEST SPIVEY UNIT Well #: 13
County: KINGMAN Total Vertical Depth: 4375 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4374		200 SX CMT.
SURF	8.625	197		250 SX CMT. \$142.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2007 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND 50' ABOVE PERFS. CAP WITH 5 SKS CMT. REC. CASING. 35 SKS @1250', 35 SKS @700', CIR CMT FROM 300'-0' PERF BETWEEN 4278'-4324'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/31/2007 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4225' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2450' AND PULLED TO 1250' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SKS OF CMT WAS SPOTTED PULLED CASING TO 300', WHERE CMT WAS CIRC. TOSURFACE, REAMAINING CASING PULLED AND CMT TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4278	4324		MISSISSIPPI

INVOICED
DATE 4-10-07
INV. NO. 2007061562

Remarks: ALLIED CEMENTING CO. - CMT 60-40 POSMIX 4%GEL TICKET #23494

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

CONSERVATION DIVISION
WICHITA, KS

PPT