

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01193-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 26-30S-8W  
330 feet from N Section Line, 1000 feet from E Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 14  
County: KINGMAN Total Vertical Depth: 4413 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4407		150 SX CMT.
SURF	8.625	195		125 SX CMT.

\$143.42

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (972) 628-1478

Proposed Plugging Method: PBTD 4364', PERFS 4292-4336', SAND BACK TO 4242 AND CAP WITH 5 SKS CMT. REC PIPE, 35 SKS 1250', 35 SKS 700' CIR 250'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/05/2007 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE SANDED BACK TO 4220', CAPPED WITH 5 SKS CMT.. NO STRETCH IN CASING WILL PERF AND SQUEEZE. ROZEL PERFORATOR CO. SHOT HOLES @ 1250', PUMPED 35SKS CMT DOWN CASING AND OUT SQUEEZE HOLES. SHUT IN WITH 500#. WOC. PERFD @250' AND CIRC. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4292	4336		MISSISSIPPI


INVOICED

DATE: 4-10-07  
INV. NO. 2007061562

Remarks: ALLIED CEMENTED CO.- COMM 3% CACL TICKET #24389

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)  
RECEIVED  
KANSAS CORPORATION COMMISSION

APR 04 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

*ra*

*PPT*