

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21996-00-00
Spot: NENE Sec/Twnshp/Rge: 30-28S-7W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: LORD Well #: 2
County: KINGMAN Total Vertical Depth: 4141 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4030		
PROD	4.5	4134		90 SX CMT. \$134.58
SURF	8.625	222		250 SX CMT.

Well Type: OG UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PBTD 4030', PERFS @ 3738-42' AND 4050'-62 SAND TO 3680 AND 4 SKS CMT, REC PIPE. 35 SKS 120', 35 SKS @ 700', CIRC CMT

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2007 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3685' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3550' AND PULLED TO 1200'. WHERE 35 SKS CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 270' WHERE CMT WAS CIRC. TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4050	4062		MISS
3738	3742		HERTHA

INVOICED
DATE 4-10-07
INV. NO. 2007061563

Remarks: ALLIED CEMENTING CO. 60/40 POS MIX WITH 4% GEL TICKET # 26161

Plugged through:

District: 02

Signed 

(TECHNICIAN) RECEIVED
STATE CORPORATION COMMISSION

APR 04 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PCT