

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20080-00-01
Spot: SESW Sec/Twnshp/Rge: 3-1S-34W
678 feet from S Section Line, 3361 feet from E Section Line
Lease Name: CAHOJ Well #: 6
County: RAWLINS Total Vertical Depth: 4332 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4329	0	w/300 sxs cmt
SURF	8.625	372	0	w/250 sxs cmt

\$ 140.79

Well Type: EOR UIC Docket No: E16643.4 Date/Time to Plug: 03/27/2007 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II Cement and 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 03/27/2007 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 372' w/250 sxs cement.
5 1/2" production casing set at 4329' w/300 sxs cement.
PBTD 4294'. TD 4329'. Estimated top of cement at 3020'.
Production casing had holes. Junk in the hole. Top of fish at 3800'.
Ran tubing to 2500' - pumped 135 sxs cement with 400# hulls.
Pulled tubing to 1200' - pumped 30 sxs cement with 100# hulls. Cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4240	4245		
4218	4222		
4200	4206		
4148	4153		
4096	4100		
4064	4070		

RECEIVED
KANSAS CORPORATION COMMISSION
APR 05 2007
CONSERVATION DIVISION
WICHITA, KS
INVOICED

Remarks: LEASE ALSO KNOWN AS C.G. KISLING #11. SWIFT SERVICES, INC. #11470 DATE 4-10-07
Plugged through: TBG INV. NO. 2007061565

District: 04 Signed Darrel Dipman
(TECHNICIAN)

MAR 29 2007

RET

SKELLY OIL COMPANY #11 C. G. KISLING
 DENVER, COLO. CTY RAWLINS
 CONTR GABBERT-JONES, INC. FIELD CAHOJ

3-1-34W
 C SE SW

E 3149 KB CM 7/12/70 CARD ISSUED 8/20/70 IP P 321 BO + 2% WTR
 LANS-KC 4096-4253
 GR 36.7

API 15-154-20.080

LOG	TOPS	DEPTH	DATUM
FOR		3638	- 489
WAB		3684	- 535
TOP		3852	- 703
DEER CR		3885	- 736
OREAD		3941	- 792
DOUG		4005	- 856
LKC "A"		4044	- 895
" "B"		4063	- 914
" "C"		4084	- 935
" "D"		4096	- 947
" "E"		4119	- 970
" "G"		4144	- 995
" "H"		4200	-1051
" "I"		4218	-1069
" "J"		4240	-1091
" "K"		4284	-1135

B 5/8" 372/250SX; 5 1/2" 4329/300SX (NO DST)
 PF 12/4249-53"J"ZN, 15/4240-45"J"ZN, 12/
 4218-22" I"ZN, 18/4200-06"H"ZN, 15/4148-
 53"G"ZN 18/4096-4100"D"ZN SWB 12 BO +
 TR WTR/2HRS (J) SWB 1 1/2 HR 17BO + 12B AC
 SWB 38 BO + TR WTR/2HRS BP SWB 2HRS REC
 27.3 BO N/W(H) AC 500NE SWB 12 BO N/W
 1HR SWB 1 1/2 HRS 17 BL, SWB 35.6BO N/W/2
 HRS SWB (I) PKR 4136 BP 4173 SWB 2HRS
 REC 11.1 BO N/W (G)/4HRS 44 BO/4HRS
 BP 4120 PKR AT 4080 TO TST(D) 4096-4100
 SWB 38 BO/3HRS T&R, POP PBD 4294

ADDITIONAL LOG TOP:

LTD 4330-1181

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS