

15-163-02912-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Rocks _____ County. Sec. 31 Twp. 9S Rge. 19W (E) _____ (W) _____
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE $\frac{1}{4}$
Lease Owner Francis Oil & Gas, Inc.
Lease Name Casey Well No. #1
Office Address 905 Palace Bldg., Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 12/29/52 19_____
Application for plugging filed. 12/29/52 19_____
Application for plugging approved. 12/29/52 19_____
Plugging commenced. 12/29/52 19_____
Plugging completed. 12/29/52 19_____
Reason for abandonment of well or producing formation. Dry Hole
If a producing well is abandoned, date of last production. _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged @ 240' with 15 sacks cement
Plugged @ 40' with 10 sacks cement

2-25-53

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Francis Oil & Gas, Inc.
Address 905 Palace Bldg., Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Meyer C. Miller, ~~Notary Public~~ (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Meyer C Miller

(Address)


SUBSCRIBED AND SWORN to before me this 24 day of February, 1953

My commission expires 9-15-53 _____ Notary Public.

22-2625 2-15-15M

PLUGGING
FILE SEC-31T-9-R-194
BOOK PAGE 23 LINE 2

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas Co.
George Herman Kaiser Farm Casey No. 1 Depth 3835
 Contractor Veeder Supply & Development Co. Pipe Set 253' of 8 5/8" casing
Cemented with 135 sacks cement
 Location Southeast Quarter (SE 1/4) Sec. 31 Twp. 9S Range 19W
 Commenced 12-19-52 Completed 12-29-52 County Rooks State Kansas

Surface soil sand	0	40	40
Sand shale	40	150	110
Shale	150	500	350
Shale shells	500	875	375
Sand	875	965	90
Shale /shells	965	1130	165
Red Bed	1130	1640	210
Anhydrite	1640	1680	40
Shale Shells	1680	2065	385
Lime Shells Shale	2065	2310	245
Lime Shale	2310	2530	220
Lime	2530	2545	15
Lime Shale	2545	2560	15
Shale Lime Shells	2560	2665	105
Lime Shale	2665	2785	120
Shale Lime Shells	2785	2960	175
Lime Shale	2960	3055	95
Shale Lime Shells	3055	3068	13
Lime Shale	3068	3425	357
Lime	3425	3485	60
Lime Cherty	3485	3515	30
Lime	3515	3725	210
Shale Lime Cherty	3725	3765	40
Conglomerate Shale	3765	3810	45
Lime Shale	3810	3835	25

Plugged @ 240' with 15 sacks cement.
 Plugged @ 40' with 10 sacks cement.

AFFIDAVIT.

STATE OF KANSAS)
 MONTGOMERY COUNTY) SS
 CONSERVATION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath,
 says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby
 know and on oath state that the above drilling log covering the Casey No. 1 Well
 in Section 31, Township 9S, Range 19W, Rooks County, Kansas, is true and correct.
 Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

BY Floyd W. Hild
 Floyd W. Hild

Subscribed and sworn to before me this 16th day of January, 1953.

Loles Lawson
 Notary Public

My commission expires: July 11, 1956.

PLUGGING
 FILE SEC 31 T 9 R 19W
 BOOK PAGE 72 LINE 2

JAN 19 1953