

Orig-State Corp. Comm
STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

Copy-B. A. Conner
WELL PLUGGING RECORD
K.A.R.-82-3-117

Copy-Mary Crump
Copy-Well File
15-163-02239-00-00

API NUMBER 15-163-None

LEASE NAME Nech

WELL NUMBER 1

SPOT LOCATION 990' FSL & 330'

SEC. 15 TWP. 9S RGE. 19 ^{FEL} (W)

COUNTY Rooks

Date Well Completed Aug 1950

Plugging Commenced 5-21-85

Plugging Completed 5-22-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Box 287, Great Bend, Kansas 67530

PHONE # (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6, Hays, Kansas

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3493 bottom 3502 T.D. 3502

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	Water		1487	8 5/8"	1492'	-0-
Production	Oil & Water		3494'	5 1/2"	3505'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Hallib & conn to csg. Pmpd 25 sx 60-40 Pozmix cmt w/10% gel, 3% CaCl, follow w/20 sx gel. Rel 5 1/2" wiper plug. Pmpd 75 sx 60-40 Pozmix, 10% gel, 3% CaCl w/5 sx hulls. Conn to annulus & pmpd 125 sx 60-40 Pozmix w/10% gel, 3% CaCl @ 2 BPM @ 500 psi. ISIP-500 psi. Rel Hallib. Cut 8 5/8" & 5 1/2" csg off 5' below GL. Capped 8 5/8" & weld on plate. P&A 5-22-85 Dennis Hamel, State Rep, on loc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No.
Address Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss. MAY 24 1985


Kaare A. Westby, Agent (employee of operator)
(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and that the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kaare A. Westby
(Address) Box 287, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 23 day of May, 1985

Velma L. Mog Notary Public

My Commission expires: February 15, 1988



Formation Record

Lease

Block

Well No. 1

FROM	TO	Formation	REMARKS
0	139	Shale and Shells	Elevation: 2072' RKB
139	655	Shale-Shells-Sand	
655	879	Shale	
879	1200	Sand-Shale	
1200	1444	Shale-Redbed-Shells	
1444	1482	Anhydrite	Top Anhydrite: 1445'
1482	1703	Redbed	
1703	2098	Redbed-Shale-Shells	
2098	2324	Shale-Shells-Lime	
2324	2391	Lime	
2391	2741	Lime and Shale	
2741	2844	Lime-Shale-Shells	
2844	3244	Lime-Shale	Tops: Toronto 3231' Howard 3008' Topeka 3033' Hessner 3212'
3244	3294	Lime	
3294	3345	Lime-Shale	Top L.K.C. 3251'
3345	3502	Lime	Top Arbuckle 3492'

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1935

CONSERVATION DIVISION
Wichita, Kansas