

Orig-State Corp Comm. Copy - B. A. Conner Copy-Mary Crump  
STATE OF KANSAS WELL PLUGGING RECORD  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Copy - B. A. Conner Copy-Mary Crump  
WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-02241-0000  
Copy Well file

API NUMBER 15-163 None

LEASE NAME Nech

WELL NUMBER 3

SPOT LOCATION 990' FEL & 2310'

NE/4  
SEC. 15 TWP. 9 RGE. 19 <sup>FNL</sup> ~~KKK~~ <sup>(W)</sup>

COUNTY Rooks

Date Well Completed March 1952

Plugging Commenced 5-21-85

Plugging Completed 5-22-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Box 287, Great Bend, Kansas 67530

PHONE # (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6, Hays, Kansas

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3503 bottom 3510 T.D. 3510

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	Water		190	8 5/8"	183'	-0-
Production	Oil & wtr		3503	5 1/2"	3526'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Hallib-pmp down csg: 25 sx 60-40 Pozmix cmt w/10% gel, 3% CaCl, follow w/20 sx gel & 175 sx 60-40 Pozmix w/10% gel, 3% CaCl w/5 sx hulls. Conn to annulus & pmpd 250 sx 60-40 Poz w/10% gel, 3% CaCl @ 2 BPM @ 500 psi. TSTP 500 psi. Rel Hallib. Cut 8 5/8" & 5 1/2" csg off 5' below GL. Cap 8 5/8" & weld on plate. Well P&A 5-22-85. Dennis Hamel, State Rep, on loc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_  
Address Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

MAY 24 1985


Kaare A. Westby, Agent (employee of operator) or 5-24-85  
(operator) of above-described well, being first duly sworn on oath, says: CONSERVATION DIVISION  
I have knowledge of the facts, statements, and matters herein contained and Wichita, Kansas  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Kaare Westby  
Kaare A. Westby, Agent  
(Address) Box 287, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 23 day of May, 19 85

Velma L. Mog  
Velma L. Mog Notary Public

My Commission expires: February 15, 1988



# Formation Record

Lease

Block

Well No.

3

FROM	TO	Formation	REMARKS
0	192	Surface sand and clay	
192	275	Clay	
275	1300	Shells and Shale	
1300	1450	Redbed and Shells	
1450	1470	Anhydrite	
1470	1950	Shale and Shells	
1950	2175	Line and Shale	
2175	2245	Line	
2245	2365	Line and Shale	
2365	2415	Line	
2415	3185	Line and Shale	Top: Howard 5010 Topeka 5057
3185	3500	Line	Tops: Hechner 3217 Toronto 3257 LKC 3255 Base LKC 3478 Arbuckle 3502'

RECEIVED  
STATE CORPORATION COMMISSION

MAY 03 1985

CONSERVATION DIVISION  
Wichita, Kansas