

STATE OF KANSAS
CORPORATION COMMISSION


WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

ROOKS County. Sec. 15 Twp. 9S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner PETROLEUM, INC.
Lease Name CASEY Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 11-4- 1963
Application for plugging filed 11-4- 1963
Application for plugging approved 11-4- 1963
Plugging commenced 11-4- 1963
Plugging completed 11-4- 1963
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3240 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				NONE	NONE	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 550', FOLLOWED BY A WOODEN PLUG & 30 SACKS CEMENT,
MUDDED UP WITH HEAVY MUD TO 180', FOLLOWED BY A WOODEN PLUG. PLACED 30 SACKS
CEMENT THRU DRILL PIPE ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD TO 40',
FOLLOWED BY A WOODEN PLUG. PLACED 40 SACKS CEMENT ON TOP OF WOODEN PLUG,
TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963
11-12-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRLG. Co.
Address R. R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R. R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 11TH day of NOVEMBER, 1963

My commission expires SEPTEMBER 23, 1967 Notary Public.

WELL LOG

15-163-19328-00-00

COMPANY Petroleum, Inc.

SEC. 15 T.9S R. 19W

FARM Casey

NO. 1

LOC. NW NW NW


TOTAL DEPTH 3240'

COUNTY Rooks

COMM. 10-31-63

COMP. 11-4-63

CONTRACTOR Garvey Drilling Company



CASING None

ELEVATION 2067' D.F.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40' Clay and Post Rock
- 950' Shale w/Sand Streaks
- 1130' Sand
- 1140' Shale and Red Bed
- 1230' Shale and Sand
- 1468' Red Bed
- 1505' Anhydrite
- 2200' Shale and Shells
- 2236' Lime and Shale
- 2325' Shale and Lime
- 2585' Lime and Shale
- 2930' Lime
- 3080' Broken Lime and Shale
- 3240' Lime and Shale
- 3240' RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Casey #1 well.

Sam N. Stephens

Subscribed and sworn to before me this 7th day of November 19 63

My Commission Expires: September 23rd, 1967

[Signature]
NOTARY PUBLIC