


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rocks _____ County. Sec. 15 Twp. 9 Rge. 19 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE SE
Lease Owner Misgrove Petroleum Corporation
Lease Name Bartos Well No. 1
Office Address 407 KFH Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 1/23/19 52
Application for plugging filed 1/23/19 52
Application for plugging approved 1/23/19 52
Plugging commenced 1/23/19 52
Plugging completed 1/23/19 52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3569 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8-5/8"	190'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 175 feet.
Set first plug at 175 feet.
Put in 1/2 sack hulls and 15 sacks cement.
Set second plug at 40 feet.
Put in 1/2 sack hulls and 10 sacks cement.

2-13-52
FEB 13 1952

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor Misgrove Petroleum Corporation, Inc.
Address 407 KFH Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 KFH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of February, 19 52
Thany Lou Raper
Notary Public.

My commission expires July 9, 1952
23-8390-s 6-51-20M

PLUGGING
FILE SEC 15 T 9 R 19 W
PAGE 44 LINE 5

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Bartos #1
 LOCATION: NE SE SE Section 15-9S-19W
 Rooks County, Kansas
 COMMENCED: January 12, 1952
 COMPLETED: January 23, 1952

0	5	Cellar
5	70	Surface soil and clay
70	110	Sandy gravel
110	187	Shale
187	550	Shale, sand and shells
550	790	Shale and shells
790	880	Sand and river gravel
880	1005	Shale and red bed
1005	1230	Sand and gravel
1230	1275	Shale and red bed
1275	1465	Shale
1465	1515	Anhydrite
1515	1825	Shale and shells
1825	2030	Shale and lime shells
2030	2180	Shale and shells
2180	2325	Shale and lime streaks
2325	2390	Shale and lime
2390	2540	Shale and lime streaks
2540	2930	Lime and shale
2930	3015	Lime streaks and shale
3015	3088	Shale and lime
3088	3159	Lime and shale streaks
3159	3299	Lime and shale
3299	3324	Lime and chert
3324	3508	Lime
3508	3540	Lime and shale
3540	3569	Lime
	3569	Rotary Total Depth

Set 190' of 8-5/8" surface casing, cemented with 160 sacks.

Dry and Abandoned.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Bartos #1, Section 15-9S-19W, Rooks County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this twenty-ninth day of January, 1952.

My Commission expires July 9, 1952.

Shary Lou Boyer
 Notary Public

2-1-52
 FEB 1 X 1952

PLUGGING
 FILE 2015 19 R 19W
 BOX 140 5