


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks _____ County. Sec. 15 Twp. 9 Rge. (E) 19 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NE

Lease Owner Harry Gore

Lease Name Nech Well No. 3

Office Address 400 Brown Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 5-22-52 19__

Application for plugging filed 6-6-52 19__

Application for plugging approved 6-9-52 19__

Plugging commenced 6-25-52 19__

Plugging completed 7-1-52 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3504 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|-----------------|--------|------------|
| | | | | 8-5/8 | 165 | none |
| | | | | 5 $\frac{1}{2}$ | 3502 | 2,622 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3530 to 3490' sand bridge

3490 to 3460' 5 sacks cement

3460 to 155' mudded

155 to 145' rock bridge

145 to 30' mud

30' to cellar 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Pipe Pulling Co.

Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Ralph Gore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HARRY GORE

(Signature) Ralph Gore By: Ralph Gore Partner

400 Brown Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 14th day of July, 1952.

My commission expires June 7, 1956

Charlotte Klitchka Notary Public.

23-8390-s 6-51-20M

PLUGGING
FILE SEC 15 T 9 R 19
BOOK PAGE 27 LINE 6

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1952
7-15-52
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: Harry Gore
 CONTRACTOR: Empire Drilling Company
 FARM: Nech #3
 LOCATION: SW NE NE Sec. 15-9-19W
 Rooks County, Kansas
 COMMENTED: 5-13-52
 COMPLETED: 5-22-52

| | | | |
|------|----|------|------------------------|
| 0 | to | 175 | Surface |
| 175 | to | 735 | Shale and shells |
| 735 | to | 805 | Sand |
| 805 | to | 1185 | Shale, shells and sand |
| 1185 | to | 1455 | Shale and shells |
| 1455 | to | 1465 | Anhydrite |
| 1465 | to | 2055 | Shale and shells |
| 2055 | to | 3015 | Shale and lime |
| 3015 | to | 3080 | Lime and shale |
| 3080 | to | 3295 | Shale and lime |
| 3295 | to | 3504 | Lime |

T.D.

Set 165' -- 3-5/8" surface pipe, cemented with 125 sacks of cement -- ran 3502' of 5 1/2" casing cemented with 100 sacks of cement.

TOPS: Topeka 3013'; Heebner 3220'; Toronto 3239'; Lansing K.G. 3259'; Arbuckle 3501'; T. D. 3504'

All depths from rotary bushing.

ELEVATION: 2076' rotary bushing.

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the Nech #3 in Section 15, Township 9, Range 10 West, Rooks County, Kansas as reflected by files of the Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 5th day of June, 1952.

Marie K. ...
 NOTARY PUBLIC

My Commission Expires 5-5-56

PLUGGING
 FILE SEC 15-9-19W
 BOOK PAGE 24 LINE 6

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 7 - 1952
 6-7-52
 CONSERVATION DIVISION