

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rooks SEC. 15 TWP 9S RGE. 19 XE/W  
 Location as in quarters or footage from lines:  
330' FNL & 1650' FEL of SE/4


Lease Owner Phillips Petroleum Company  
 Lease Name Nech Well No. 4  
 Office Address Box 287, Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed May 20, 1952  
 Application for plugging filed September 22, 1982  
 Plugging commenced October 20, 1982  
 Plugging completed October 20, 1982  
 Reason for abandonment of well or producing formation Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
 Producing formation Arbuckle Depth to top 3506 bottom 3509 T.D. 3509  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	207'	8 5/8	210'	-0-
Production	Oil & Wtr	0'	3506'	5 1/2	3502'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set. MIRU Halliburton to 5 1/2" csg & pmpd 25 sx 50-50  
Pozmix w/ 1/2 sk hulls, followed by 16 sx gel & 110 sx 50-50 Pozmix w/6% gel & 2 1/2 sx  
hulls. Press to 1000 PSI - press held. Conn to 8 5/8" & press to 200 PSI. Cut  
off pipe 4 1/2' below GL. Weld on plate. Well P&A 10-20-82

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Halliburton Services  
Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
C. D. Dohrer (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed, and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Manager  
Box 287, Great Bend, Kansas 67530  
 (Address)



SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 82  
Velma L. Mog  
 Velma L. Mog  
 Notary Public.

My Commission expires: February 15, 1984

STATE CORPORATION COMMISSION

OCT 26 1982  
 10-26-82  
 CONSERVATION DIVISION  
 Wichita, Kansas

# Formation Record

Lease

Neek

Well No.

4

FROM	TO	Formation	REMARKS
0	210	Surface sand and shale	
210	250	Shale	
250	1278	Shale and Sand	
1278	1770	Shale, redbed and Anhydrite	
1770	2167	Redbed, Shale and Lime Streaks	
2167	2317	Lime streaks and Shale	
2317	2689	Lime and Shale	
2689	2836	Pyrite, Lime and Shale	
2836	3126	Lime and Shale	
3126	3257	Lime	
3257	3393	Lime, Chert and Shale	
3393	3455	Lime	
3455	3509	Lime and Shale	

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1982  
9-23-82  
CONSERVATION DIVISION  
Wichita, Kansas

Tops:	Howard	3017
	Topeka	3043
	Heeoner	3222
	Toronto	3242
	L.K.C.	3262
	Base L&C	3432
	Marmaton	3496
	Arbuckle	3505