

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

OKC 15-163-03002-00-00  
API NUMBER 15-163-Prior to '67

LEASE NAME Nech

WELL NUMBER 5

SPOT LOCATION 1650'FSL & 2210'

SEC. 15 TWP. 9S RGE. 19 <sup>FEL</sup> or (W)

COUNTY Rooks

Date Well Completed 1952

Plugging Commenced 8-18-84

Plugging Completed 8-22-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Box 287, Great Bend, Kansas 67530

PHONE # (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3519' bottom 3521' T.D. 3521'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation  | Content     | From | To   | Size   | Put in | Pulled out |
|------------|-------------|------|------|--------|--------|------------|
| Surface    | Water       | 0'   | 205  | 8 5/8" | 198    | -0-        |
| Production | Oil & Water | 0'   | 3519 | 5 1/2" | 3514   | -0-        |
|            |             |      |      |        |        |            |
|            |             |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Hallib & pmpd 25 sx 50-50 Poz w/6% gel & 3% CaCl, 1 sk hulls, follow w/20 sx gelled mud w 4 1/2 sx hulls, 1 - 5 1/2" 17# wiper plug, 125 sx 50-50 Poz, 6% gel, 3% CaCl, 1/2 sk hulls to 500 psi-held, Conn to annulus. Press annulus to 500 psi-could not pmp in. Rel Hallib. Cut off csg 6' below GL. Well P&A 8-22-84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_  
Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Kaare A. Westby, Agent

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as presented to me are true and correct, so help me God.


RECEIVED  
AUG 28 1984  
8-28-84  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Kaare A. Westby  
Kaare A. Westby, Agent  
(Address) Box 287, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1984

Velma L. Mog  
Notary Public

My Commission expires: February 15, 1988



## Formation Record

Lease Nech

Well No. 5

| FROM | TO   | Formation                | REMARKS                         |
|------|------|--------------------------|---------------------------------|
| 0    | 210  | Surface clay.            |                                 |
| 210  | 921  | Shale, sand and pyrite.  |                                 |
| 921  | 1680 | Sand, shale and red bed. |                                 |
| 1680 | 2016 | Shale and lime streaks.  |                                 |
| 2016 | 2368 | Lime and shale.          |                                 |
| 2368 | 2532 | Shale.                   |                                 |
| 2532 | 2780 | Lime and shale.          |                                 |
| 2780 | 3051 | Shale and lime streaks.  | Top: Howard 3031'.              |
| 3051 | 3232 | Lime and shale.          | Topoka 3059'.                   |
| 3232 | 3306 | Cherty lime and shale.   | Heebner 3236'. Toronto 3260'.   |
| 3306 | 3377 | Lime.                    | Lansing-Kansas City 3278'.      |
| 3377 | 3429 | Lime and shale streaks.  |                                 |
| 3429 | 3521 | Lime and shale.          | Base LKC 3497'. Arbuckle 3518'. |

RECEIVED  
STATE CONSERVATION COMMISSION

AUG 28 1984

CONSERVATION DIVISION  
Wichita, Kansas

Form No. 879

## Formation Record

Lease Book

Well No. 5

| FROM | TO   | Formation                | REMARKS   |
|------|------|--------------------------|---|
| 0    | 210  | Surface clay.            |   |
| 210  | 921  | Shale, sand and pyrite.  |   |
| 921  | 1680 | Sand, shale and red bed. |   |
| 1680 | 2016 | Shale and lime streaks.  |   |
| 2016 | 2368 | Lime and shale.          |   |
| 2368 | 2532 | Shale.                   |   |
| 2532 | 2780 | Lime and shale.          |   |
| 2780 | 3051 | Shale and lime streaks.  | Tops: Howard 3031'.   |
| 3051 | 3232 | Lime and shale.          | Topeka 3059'.   |
| 3232 | 3306 | Cherty lime and shale.   | Heebner 3236', Toronto 3260',<br>Lansing-Kansas City 3278'. |
| 3306 | 3377 | Lime.                    |   |
| 3377 | 3429 | Lime and shale streaks.  |   |
| 3429 | 3521 | Lime and shale.          | Base LKC 3497'. Arbuckle 3518'.                             |