

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-22,908-00-00

LEASE NAME Novotny

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 15 TWP. 9 RGE. 19 (XXXX) (W)

COUNTY Rooks

Date Well Completed 1-3-87

Plugging Commenced 1-3-87

Plugging Completed 1-3-87

LEASE OPERATOR Abercrombie Drilling, Inc. & Conch Oil, Inc.

ADDRESS 801 Union Center, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422 & 4388

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6, state plugger Dale Balthazar

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	225	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump heavy mud to 3505'-3405', 25 sacks; pump heavy mud to 1470'-1370', 25 sacks; pump heavy mud 820'-420', 100 sacks and 1 sack celoflake; pump heavy mud to 250'-90', 40 sacks; pump heavy mud to 40' to solid bridge, 10 sacks; 10 sacks in the rathole; all cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 810 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Secretary/Treasurer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) Jack K. Wharton
801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1987

Clarice M. Mize
 Clarice M. Mize Notary Public
 STATE CORPORATION COMMISSION

My Commission Expires: November 28, 1988

1-12-87
 JAN 12 1987 Form CP-4
 Revised 07-86
 CONSERVATION DIVISION
 Wichita, Kansas