

RECEIVED

12-26-01
DEC 26 2001

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-163-23,007-00-00 (identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Bowman Oil Company KCC LICENSE # 6931
(owner/company name) (operator's)

ADDRESS 805 Codell Road CITY Codell

STATE Kansas ZIP CODE 67663 CONTACT PHONE # (785) 434-2286

LEASE Novotny WELL# 1-15 SEC. 15 T. 9 R. 19 (East/West)

SE . SW . NE . SPOT LOCATION/QQQQ COUNTY Rooks

2970 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 227 CEMENTED WITH 135 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3500 CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2075 T.D. 3503 PBDT _____ ANHYDRITE DEPTH 1500
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING _____

Cement well top to bottom according to KCC Dist # 4

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Bowman PHONE# 785 434-7202

ADDRESS 805 Codell Road City/State Codell, KS

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # _____
(company name) (contractor's)

ADDRESS Russell, KS PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Jan 3, 2002

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: Don Bowman
(signature)

Operator Name Lansing Energy Corporation Lease Name Novotny 'B' Well # 1-15

Sec. 15 Twp. 9 Rge. 19 East West County Rooks

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No

Formation Description
 Log Sample

DST 3299-3361, Rec. 365' MGSW, W/ tr oil and 365' of GSW, SIP 829-722#
 DST 3369-3420, Rec. 450' MGSW, SIP 778-737#
 DST 3422-3463, Rec. 5' Mud, SIP 471-74#

Name	Top	Bottom
Heebner	3214(-1139)	
Toronto	3236(-1164)	
Lansing	3256(-1181)	
BKC	3462(-1387)	
Arbuckle	3498(-1423)	
RTD	3503(-1428)	

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface Production	12 1/8"	8 5/8"	20#	227'	60/40 poz	135	3%cc/2% gel
	7 7/8"	5 1/2"	10.5	3500'	ATL	250	
					60/40poz	150	10% salt/5% gilson
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)			
Shots Per Foot	Specify Footage of Each Interval Perforated			Depth			
				300 GAL MCA			3500-06
TUBING RECORD				Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Size	Set At	Packer at					
2 7/8"	3477'						
Date of First Production	Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (explain).....						
11-30-88							
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio		Gravity	
	4 BO Bbls		350 BW Bbls				

METHOD OF COMPLETION

Disposition of gas: Vented Open Hole Perforation
 Sold Other (Specify)
 Used on Lease Dually Completed Conningled

Production Interval 3500-3506



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bowman Oil Company
805 Codell Rd.
Codell, KS 67663

January 02, 2002

Re: NOVOTNY #1-15
API 15-163-23007-00-00
CSESWNE 15-9S-19W, 2970 FSL 1650 FEL
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550