

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

15-103-02241-0000

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER drld in March, 1952 (of this well) 6/85  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Phillips Petroleum Company OPERATORS LICENSE NO. 5229

ADDRESS P. O. Box 287, Great Bend, Kansas 67530 PHONE # (316) 793-8421

LEASE (FARM) Nech WELL NO. 3 WELL LOCATION FNL, NE/4 of COUNTY Rooks

SEC. 15 TWP. 9S RGE. 19 ~~EX~~ or (W) TOTAL DEPTH 3510' PLUG BACK TO 3510'

Check One:

OIL WELL XX GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" 24#/SET AT 190' CEMENTED WITH 175 (circ.) SACKS

CASING SIZE 5 1/2" 14#/SET AT 3503' CEMENTED WITH 150 SACKS

Also through DV collar at 1463' w/375 sx, cmt circ.

PERFORATED AT Open hole 3503-10'

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 30 sx 50-50 Pozmix with 6% gel and 3% CaCl and hulls. 20 sx gel (60 bbls. 9#/gal. mud with hulls). 5 1/2" wiper plug followed with 125 sx 50-50 Pozmix with 6% gel and 3% CaCl. Pump into annulus with 50-50 Pozmix with 6% gel and 3% CaCl. (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 15, 1985 at 8:00a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et sec AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: H. G. Stearns

H. G. Stearns PHONE # (913) 434-4638

ADDRESS P. O. Box "J", Plainville, KS 67663

PLUGGING CONTRACTOR Not Applicable LICENSE NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Kaare Westby  
(Operator or Agent)

DATE: May 1, 1985

RECEIVED

STATE CORPORATION COMMISSION

MAY 03 1985

5/3/85  
CONSERVATION DIVISION

Wichita, Kansas

0



PHILIP CARLIN  
MICHAEL LENNEN  
ARGALEE WRIGHT  
RICHARD R. HENLEY  
EDITH A. McCONNELL  
TIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 6 1985

May 6, 1985

EXPIRES

WELL PLUGGING NOTICE

Nech #3  
990'FEL 2310'FNL NE/4  
Sec. 15-9S-19W  
Rooks County

Phillips Petroleum Company  
P. O. Box 287  
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).