

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-22,672-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Mark 111 Oil, Inc. OPERATORS LICENSE NO. 5633

ADDRESS 3000 Broadway Suite D Hays, Kansas 67601 PHONE # (913) 628-6214

LEASE (FARM) Allen WELL NO. 1 WELL LOCATION NW-SE-NE COUNTY Rooks

SEC. 11 TWP. 9 RGE. 20 (E) or (W) (W) TOTAL DEPTH 3635 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 253' CEMENTED WITH 150 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st Plug @ 3615 w/ 20 sks, 2nd Plug @ 1600

W/ 20 sks, 3rd Plug @ 920 W/ 100 sks, 4th Plug @ 300' W/40 sks & 1 sk Celloflote, 5 th Plug

@ 40' W/ 10 SkS & 1 sk Hulls. 10 sks in Rat Hole 50-50 Pos 6% Gel 3 % C.C.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5-14-85 Plug Down @ 1:00 PM.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: RECEIVED

D.J. Markley PHONE # (913) 628-6214 STATE CORPORATION COMMISSION

ADDRESS 3000 Broadway Suite D Hays, Kansas 67601 5/23/85
MAY 23 1985

PLUGGING CONTRACTOR Jay-Lan Corporation LICENSE NO. 5128 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS 207 W. 12th Hays, Kansas 67601 PHONE # (913) 628-3834

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: D.J. Markley
Operator or Agent

DATE: 5-27-85