

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22566-00-00

LEASE NAME Newell

WELL NUMBER 1

SPOT LOCATION NE NE SE

SEC. 7 TWP. 9S RGE. 20 ~~XE000~~ (W)

COUNTY Rooks

Date Well Completed 11-24-1984

Plugging Commenced 11-24-1984

Plugging Completed 11-24-1984

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Helberg Oil Company

ADDRESS Box 32 Morland, Ks. 67650

PHONE # (913) 627-5665 OPERATORS LICENSE NO. 5669

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays Office

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	215'	8 5/8"	215'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st. Plug set at 1740' with 20 sacks common cement 50-50 Poz 6%Gel 3%Cal cl.
2nd. plug set at 1030' with 100 sacks common cement and 1 sack flo-seal 50-50 Poz 6%Gel 3%Cal c
3rd. Plug set at 250' with 40 sacks common cement 50-50 Poz 6%Gel 3%Cal cl.
4th plug set at 40' with 10 sacks common cement, solid bridge and hulls, 50-50 Poz 6%Gel 3%Cal c
10 sacks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Oilwell Cementing License STATE CORPORATION COMMISSION
Address Hays, Ks. 67601

RECEIVED
12/14/84
DEC 14 1984

STATE OF Kansas COUNTY OF Graham, ss.

CONSERVATION DIVISION
Wichita, Kansas


Jerry M. Helberg (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. I also help me God.

(Signature) Jerry M. Helberg

(Address) Box 32 Morland, Ks. 67650

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1984

Coleen A. Waggoner
Notary Public



My Commission expires: March 11, 1986