


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 33 Twp. 9 Rge. 19 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines SW SE SW
Lease Owner Okmar Oil Co.
Lease Name Hamel Well No. #3
Office Address 1130 Vickers KSB&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 1-12-73 19
Application for plugging approved 19
Plugging commenced 2-8-73 19
Plugging completed 2-15-73 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3746' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3740'	734.73'
				8 5/8"	176'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3700'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 3 sacks hulls - 20 sacks gel and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1973
2-20-73
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of February, 1973

My commission expires October 1976
Sidney D. Miller
Notary Public.



L. B. STABLEFORD
HAMEL # 3

SW SE SW Sec. 33-95-19W
Rooks County, Kansas

Casing

8 5/8" Set @ 176
5 1/2" Set @ 3740

Cement

100 Sacks
125 Sacks

Comm: 7-23-51
Comp: ~~7-21-51~~ 8-5-51
Total Depth: 3746'

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1973
1-16-73
CONSERVATION DIVISION
Wichita, Kansas

FORMATION

DEPTH

Surface clay & sand	0 - 135
Sand	135 - 155
Shale	155 - 178
Shale & shells	178 - 615
Shale & sand	615 - 1075
Sand	1075 - 1135
Shale & sand	1135 - 1425
Red bed & shale	1425 - 1600
Anhydrite	1600 - 1638
Shale & red bed	1638 - 1780
Shale & lime	1780 - 3380
Lime	3380 - 3450
Lime & shale	3450 - 3555
Cherty lime & shale	3555 - 3580
Shale & lime	3580 - 3685
Shale, lime & chert	3685 - 3705
Cherty lime & shale	3705 - 3747

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I hereby certify that the above information is true and correct
to the best of my knowledge.

L. B. Stableford

Subscribed and sworn to before me this 5th day of September, 1951.



My commission expires: 6-5-54

L. B. Stableford

Notary Public