

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 33 Twp. 9 Rge. 19 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner Sierra Petroleum Co., Inc.

Lease Name Richardson

Well No. 3

Office Address 211 North Broadway, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed November 1956

Application for plugging filed June 1969

Application for plugging approved June 12 1969

Plugging commenced July 13, 1969

Plugging completed July 15, 1969

Reason for abandonment of well or producing formation not economical

If a producing well is abandoned, date of last production 10-17 1968

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Lansing Kansas City Depth to top 3435 Bottom 3639 Total Depth of Well 3741 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	oil & water	3410	3514	8 5/8	169'	none
				5 1/2	3737 1/2'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PBTD 3564' in 9-1968. Cast iron plug w/lsx. cement.

Sanded in from 3564' to 3400', dumped 4 sx. cement on top of sand.

Pumped 5 sx. hulls and 15 sx. Gell down 8 5/8 surface pipe. Followed with pump plug and 100 sx. posmix cement with 6% gell added. Left cement standing at top of 8 5/8 pipe.

RECEIVED
STATE CORPORATION COMMISSION
7-22-69
JUL 22 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing and Pulling Co.

Address Box 221, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Preston J. Burkey

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature)

Preston J. Burkey

211 N. Broadway Wichita, Kansas 67202

(Address)


SUBSCRIBED AND SWORN to before me this 21 day of July, 1969

Patricia Menasco

Notary Public.

My commission expires

July 7, 1971




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company MALLONEE DRILLING COMPANY, INC., ET AL
Farm Richardson No. 3

SEC. 33 T. 9 R. 19W
SW SE NW

Total Depth. 3741'
Comm. 10-13-56 Comp. 10-26-56
Shot or Treated.
Contractor. Mallonee Drilling Company,
Issued. 2-16-57

County Rocks KANSAS



CASING:

8 5/8" 2169' w/115 sx. con.
5 1/2" 3373 1/2' w/75 sx. con.

Elevation. 2219' RB

Production. 30 BOPD

Figures indicate Bottom of Formations.

surface soil
& clay 15
sand & shale 50
sandy shale 95
shale & shells 169
shells, shale &
sand 350
shale & sand 1000
shale & shells 1340
shale & red bed 1615
Anhydrite 1655
shale & shells 2125
lime & shale 3315
lime 3638
lime & shale 3720
lime 3741 RTD
Total Depth

TOPS
Topeka 3180
Heebner 3392
Lansing 3495
Base/Kansas
City 3639
Shaley
Conglomerate 3659
Cherty
Conglomerate 3679
rubble 3737

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1969
CONSERVATION DIVISION
Wichita, Kansas