

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

ROOKS

County. Sec. 33 Twp. 9 Rge. 19 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SE

Lease Owner W. L. Hartman

Lease Name Sparks Well No. 1

Office Address P. O. Box 54, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-5-52 19

Application for plugging filed 6-5-52 19

Application for plugging approved 6-6-52 19

Plugging commenced 6-13-52 19

Plugging completed 6-23-52 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3745 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	188'	
				5-1/2"	3745'	2243'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3745 to 3710 Sand
 3710 to 3680 5 sacks cement
 3680 to 190 Mudded
 190 to 180 Rock bridge
 180 to 125 15 sacks cement
 125 to 30 Mud
 30 to cellar 10 sacks cement

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 2 1952
 7-2-52
 CONSERVATION DIVISION
 WICHITA, KANSAS

Correspondence regarding this well should be addressed to W. L. Hartman
Address P. O. Box 54
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. Hartman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Hartman
P. O. Box 54, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 1952

Georgia L. Lard
Notary Public.

My commission expires May 13, 1953

PLUGGING
 FILE SEC 33 T 9 R 19
 BOOK PAGE 21 LINE 28

SPARKS NO. 1 WELL

LOCATION: SW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$ 33-98-19W
Rooks County, Kansas

OPERATOR: W. L. Hartman

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Set 8-5/8" casing at 188' with
125 sacks cement and 1 c.c.

OIL STRING: Cemented 5 $\frac{1}{2}$ " J-55 11# at 3745'
with 25 sacks cement.

SPUDDED: 4-25-52

COMPLETED: 5-6-52

LOG

(Figures indicate bottom of formation)

0 to 75	Clay, shells and sand
1225	Shale and shells
1590	Shale and red bed
1630	Anhydrite
1690	Shale
2130	Shale and shells
3065	Shale and lime
3310	Shale and shells
3360	Lime and shale
3645	Lime
3695	Lime and chert
3733	Cherty conglomerate
3736	Dolomite
3740	Lime, shale and chert
3742	Shale
3745	Lime
3745	Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Sparks No. 1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me
this 7th day of May, 1952.

Virian L. Linger
Notary Public

My commission expires November 29, 1954.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 2 1952
7-2-52
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 33 T 9 R 19W
BOOK PAGE 21 LINE 28