

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Rooks County. Sec. 31 Twp. 9N Rge. 19W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$  NW $\frac{1}{4}$  NW $\frac{1}{4}$

Lease Owner Frontier Oil Company

Lease Name C Steeples

Well No. 1

Office Address 612 Union National Bank Bldg. Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 10- 19 53

Application for plugging filed July 10- 19 53

Application for plugging approved July 10- 19 53


Plugging commenced July 10- 19 53

Plugging completed July 10- 19 53

Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Pettie

Producing formation Depth to top Bottom Total Depth of Well 3826 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Clay and Sand	none	0	155	8 5/8"	155'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from bottom of hole to 155' Set permanent plug and cemented with 15 sacks of cement. Filled hole again to 30' with heavy mud. placed another permanent plug and cemented with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Adkins Drilling Company, Inc.  
Address P O Box 724 Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

Jim Adkins (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Adkins

P O Box 724 Great Bend, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1953

My commission expires 2-29-1956.

Pauline B. Adkins  
Notary Public.

PLUGGING  
FILE SEC 31 T 9 R 19W  
BOOK PAGE 114 LINE 39

7-17-53

Drillers Drilling Report

Lease Owner ----- Frontier Oil Company, 612 Union National Bank Bldg. Wichita, Kansas.

Lease -- G. Steeples No. 1

Location ----- NW $\frac{1}{4}$  NW $\frac{1}{4}$  NW $\frac{1}{4}$  Sec. 31-9-19N. Rooks County, Kansas.

Contractor-- Adkins Drilling Company, Inc. Great Bend, Kansas.

Formation	From	To	Formation	From	To
Surface Clay, and sand	0	155	Shale & Lime	3205	3365
Set 155' of 3 5/8" at 155'			Lime	3365	3732
cemented it with 125 sacks of cement 1 sack Ca Cl.			Lime & Chert	3732	3735
Plug and Cement	122	155	Conglomerat(cherty)	3735	3776
Sand, clay & shells	155	570	Lime & Chert	3776	3782
Shale	570	570	Conglomerat	3782	3811
Sand & Shale	570	1420	Dolomite	3811	3826
Shale	1420	1640			
Shale & Red Bed	1640	1900	F. D.	3826	
Shale & Lime	1900	2269	Dry & Abandoned @	3826'	
Lime & Shale	2269	2387			
Shale & Lime	2387	2672			
Shale	2672	3205			

State of Kansas. }  
County of Barton } ss.

7-17-53

Jim Adkins President of the Adkins Drilling Company, Inc. of Great Bend, Kansas, does solemnly swear that the foregoing is a true and correct copy of the Drillers Log on Steeples No. 1 to the best of his knowledge and belief.

Subscribed and sworn to before me this 14th day of July 1953.

Pauline B. Adkins  
Notary Public

My Commission expires 2-29-56

PLUGGING  
FILE SEC 31 T 9 R 190  
BOOK PAGE 114 LINE 39