

4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 31 Twp. 9 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines SW-SW-SW

Lease Owner Francis Oil & Gas Inc.

Lease Name Pywell Well No. 1

Office Address 905 Palace Bldg. Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-31 1950

Application for plugging filed 1-31 1962

Application for plugging approved 2-1 1962

Plugging commenced 2-7 1962

Plugging completed 2-13 1962

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3770 Bottom 3774 Total Depth of Well 3774 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	184	None
				5 1/2	3770	1240

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" 184' circulated W/cement.
5 1/2" 3770' W/125 sacks cement behind. Filled w/sand to 3760', set 4 sacks cement W/dump bailer @ 3760'. Pulled 1240' 5 1/2" to 510' circulated hole W/ heavy gel mud through 5 1/2" @ 510' (40 sacks gel), displaced 20 sacks cement through 5 1/2" @ 500', heavy mud to 150', displaced 20 sacks cement through 5 1/2" @ 150', heavy gel mud to 35' set bridge and filled hole to bottom cellar W/cement.
Mudding W/ and cementing by Globe Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1962
3-14-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R&D Casing Pulling Co. & Globe Cementing Co.

Address Hutchinson, Kansas Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

I, W.J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 666, Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13 day of March, 1962

My commission expires

[Signature]
EVELYN L. MILLER, NOTARY PUBLIC
Commission Expires Feb. 25, 1963



