

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 14 Twp. 9 Rge. 19 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW NW NE

Lease Owner Theodore Gore

Lease Name Ruder Well No. 3

Office Address 650 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed September 19, 1948 19

Application for plugging filed January 5, 1962 19

Application for plugging approved January 8, 1962 19

Plugging commenced January 8, 1962 19


Plugging completed January 24, 1962 19

Reason for abandonment of well or producing formation _____

went to water

If a producing well is abandoned, date of last production December 28, 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Kansas City Depth to top 3210 Bottom 3214 Total Depth of Well 3473 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	164	none
				5 1/2"	3473	2800*

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug down to 3190'; sanded up to 3150'; dumped 4 sacks cement with dump bailer. Shot pipe loose at 2800'; pulled pipe up to 550'; pumped 25 sacks mud and 20 sacks cement; pulled pipe to 160'; pumped 20 sacks cement, pulled pipe out. Bailed mud down, set 10' rock bridge; dump 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1962
2-13-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Company

Address Hoistington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Theodore Gore (Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore

650 Fourth National Bank Bldg., Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 62

My commission expires October 21, 1962.

Lucille H. Harr
Lucille H. Harr

Notary Public.



Harry Gore
 RUDER #3
 Total Depth 3472'

New Sew No
 Sec. 14, Twp. 9, Rge. 19
 Rooks County, Kansas

Casing
 8 5/8" Set@ 164' w/ 150 Sax
 5 1/2" Set@ 3471' w/ 100 Sax
 Comm: 9/8/48 Comp: 9/19/48

Tops
 Heebner Shale - 3191'
 Lansing K.C. #1-3210'
 Lansing K.C. #2-3230'
 Arbuckle 3470'

Formation:	Depth:
Surface Clay	45
Sand	75
Shale & Shells	350
Sand	400
Shale & Shells	710
Sand & Shale	915
Sand	1210
Red Bed & Shale	1424
Anhydrite	1466
Shale & Shells	1895
Lime & Shale	3165
Lime	3210
Shale	3221
Lime	3410
Lime & Shale	3470
Arbuckle	3472

RECEIVED
 STATE DEPARTMENT OF COMMISSION
 SEP 17 1948
 2-13-62
 ZONE LOCATION DIVISION
 Topeka, Kansas

STATE OF KANSAS)
) SS
 RUSSELL COUNTY)

I Hereby certify that the above information is true and correct to the best of my knowledge.

Jane Duncan

Subscribed and sworn to before me this 22nd day of September, 1948.

Clara L. Linn

 Notary Public

My Comm. expires 6/17/50