

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County. Sec. 9 Twp. 9 Rge. 20 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW NW

Lease Owner I. O. Miller Oil Company

Lease Name Whisman Well No. B-2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced 1/13/67 _____ 19____

Plugging completed 1/16/67 _____ 19____

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3720 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	349	none
				5 1/2	3768	2920

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, checked bottom, ran sand to 3758'. Dumped 5 sacks cement with 3" dump bailer. Cleaned out cellar. Rigged up on 5 1/2", had 10" tension. Shot pipe at 3017', worked pipe, no gain. Shot pipe at 2909', worked pipe loose and pulled 60 joints. Had trouble with slips, pipe was muddy. Pulled 30 joints of 5 1/2", cleared floor, loaded junk rack. Bailed hole to 249', set 10' rock bridge and dumped 5 yards of ready mix. Racked unit, tallied pipe. Cleaned up braden head.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
1/26/67
JAN 26 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of Jan, 1967

My commission expires Oct -22-1970

Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR I. O. Miller WELL NAME Whisman "B" #2
 LOCATION NE NW NW SEC. 9-9-20W RIG NO. 1
 COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE November 29, 1958 COMPLETION DATE December 7, 1958

LOG OF WELL

Elevation 2230' kelly bushing.
 All measurements taken from the top of kelly bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	190	Shale-Sand		
190	210	Shale-Sand		
210	540	Shale-Sand		
540	1265	Sand-Shale		
1265	1510	Sand		
1510	1570	Red Bed		
1570	1744	Shale-Red Bed		
1744	1782	Anhydrite		
1782	2100	Shale-Shell		
2100	2295	Shale-Lime		
2295	2490	Lime-Shale		
2490	2605	Lime-Shale	0° - 2500	
2605	2810	Shale-Shell	0° - 2750	
2810	2940	Lime-Shale		
2940	3130	Lime-Shale	0° - 3000	
3130	3260	Shale-Lime	0° - 3250	
3260	3370	Lime-Shale		
3370	3468	Lime-Shale		
3468	3513	Lime-Shale		
3513	3570	Lime-Shale		
3570	3625	Lime		
3625	3655	Lime		
3655	3730	Lime-Shale		
3730	3759	Lime		
3759	3770	Lime		DST 3747-3759' DST 3758-3770'

RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1967

CONSERVATION DIVISION
 Wichita, Kansas

CASING LEFT IN HOLE AFTER COMPLETION

Ran 210.92' (10 jts.) 8-5/8" OD Surface Casing.
 Set 5-1/2" OD Casing @3748' (50 jts.)

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th day of December, 1958.

Vicky Jacobs
 Vicky Jacobs, Notary Public

My Commission expires:

May 29, 1959