

STATE OF KANSAS
STATE CORPORATION COMMISSION

COPY OF

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks County, Sec. 9 Twp. 9 Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner I O Miller Oil Co.

Lease Name Whisman Well No. # 3

Office Address P O Box 274 Ellis, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed yes 19

Application for plugging approved yes 19


Plugging commenced 12-29-60 19

Plugging completed 1-1-61 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division* or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3676' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,014'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 12-29-60. Plugging completed 1-1-61.
Measured in to total depth, 3676'.
Plugged off bottom: Sanded back from 3676' to 3650' and dumped 4 sacks of cement.
Worked and shot casing. Spotted 70 barrels oil.
Worked and shot 5 1/2" casing free at 1,014'. Built rack and slide. Pulled and layed down casing.
Plugged well: Circulated 24 sacks of cement mud at 500' and spotted 20 sacks of cement. Mudded up to 170' and spotted 20 sacks of cement. Mudded up to 35' and spotted 10 sacks of cement.

2/1/61

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 19 61

Kayanna Jenkins
Notary Public.

My commission expires December 8th, 1963



Whisman A #3 - SE SE SW Section 9-9-20 Rocks County, Kansas
 Company - I. O. Miller
 Contractor - Virginia Drilling Co Inc.
 Commenced - June 16, 1958
 Completed rotary hole - June 28, 1958
 Elevation - 2152 D F
 Total rotary depth - 3692

8 5/8" set at 244 w/140 sz con.
 5 1/2" inch set at 3682 w/125 sz con.

<u>FORMATION</u>	<u>DEPTH</u>	
Sand & shale	0-244	
Sand & shells	244-1150	
Sand	1150-1390	TOPS:
Shale	1390-1430	
Shale & shells	1430-1670	3354 - Reamer
Cherty	1670-1705	3375 - Forams
Shale & redbed	1705-1800	3393 - Lansing
B lime & shale	1800-2250	3612 - Base K0
Lime	2250-2440	3658 - Armatia
Lime & shale	2440-3350	
Lime	3350-3692 T.D.	

Walter G. Hartman

Subscribed and sworn to before me, a Notary Public, this
1st day of July, 1958.

J. W. Underwood
 Notary Public

My commission expires: March 15, 1962

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1962
 CONSERVATION DIVISION
 Wichita, Kansas