


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County, Sec. 8 Twp. 9 Rge. 20 ~~(E)~~ W (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner C-G DRILLING CO. & DANE G HANSEN TRUST
Lease Name THYFAULT Well No. 3
Office Address 1107 UNION NATIONAL BLDG.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed May 23 19 70
Application for plugging filed May 23 19 70
Application for plugging approved May 23 19 70
Plugging commenced May 23 19 70
Plugging completed May 23 19 70
Reason for abandonment of well or producing formation Dry Hole
Too low structurally
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo F. Massy
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	176.21	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 720'. Set plug with 70 sacks cement. Filled with heavy mud to 180'. Set plug with 20 sacks cement. Filled with heavy mud to 40'. Set plug. Filled to top with muds and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
6/12/70
JUN 12 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 1107 Union National Bldg, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. Galloway 1107 Union Natl Bldg.
(Address)

Subscribed and sworn to before me this 6th day of June, 19 70

My commission expires December 7, 1971
Phyllis Buchanan
Phyllis Buchanan
Notary Public.



15-163-20309-0000

W E L L L O G

OPERATOR: C-G DRILLING CO.

WELL NAME: THYFAULT #3 LOCATION: NW SE NW

COUNTY: ROOKS STATE: KANSAS

WELL COMMENCED: 5/16/70 WELL COMPLETED: 5/23/70

ELEVATION: 2167 KB TOTAL DEPTH: 3713

PRODUCTION: DRY & ABANDONED RIG NO: 1

CASING - 8-5/8": SET 5 JTS 8 5/8" W/140 SACKS POXMIX (20#)

5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1010	SAND	3/4° 1460'	
1010	1545	RED BED	1 1/2° 1460'	
1545	1643	RED BED		
1644	1686	ANHYDRITE		
1686	2095	SHALE & SHELLS	2 1/4° 2000'	
2096	3415	LIME & SHALE		
3415	3713	LIME		

DST #1 3541-67
DST #2 3571-85
DST #3 3704-13

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 8th day of June, 1970.

MY COMM. EXP. DEC. 7, 1971

Phyllis Buchanan
PHYLLIS BUCHANAN - NOTARY PUBLIC

