

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 13 Twp. 2 Rge. (E) 19 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$

Lease Owner Harbar Drilling Company et al.

Lease Name Hilgers Well No. 1

Office Address 1019 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-16-47 19.


Application for plugging filed Verbal 5/11/47 19.

Application for plugging approved 5/11/47 19.

Plugging commenced 5/11/47 19.

Plugging completed 5/12/47 19.

Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production..... 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. O. Stough

Producing formation None Depth to top..... Bottom..... Total Depth of Well 3584 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sands	Fresh water	surface	200	10 3/4" 5 1/2"	232 3550	None 2900

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled 1/2 hole with mud from 3535 to 3434

Dumped 10 sacks cement at 3434

Filled hole with mud from 3280 to 240'

Set wood plug at 240' and dumped 15 sx. cement

Filled hole with mud to 15' surface and filled casing and bottom cellar with 10 sx. cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Company
Address 1019 Central Bldg.
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, SS.

Don S. Packer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of May, 19 47

My commission expires Dec 23, 1950

Mary R. Prasad
Notary Public.

PLUGGING
FILE SEC 13 T 9 R 19W
BOOK PAGE 110 LINE 33

HARBAR-GLICK ET AL

HILGERS #1

Center NE $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$ of Sec. 13-9S-19W, Rooks County, Kansas.

Rigging up rotary tools	3-19-47	Run 8 Jts. 258' of 10 3/4" O.D. surface pipe
Tearing out rotary tools	4-5-47	Set at 232' and cemented with 130 sacks of cement.
Rigging up cable tools	4-5-47	Run 111 Jts. 3555' of 5 1/2" OD casing, cemented
Tearing out cable tools	4-14-47	1 foot off bottom with 125 sacks of cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	0	100
Sand	100	180
Shale and shells	180	237
Shale	237	660
Sand	660	800
Shale and shells	800	1000
Sand	1000	1200
Shale	1200	1330
Shale and sand	1330	1530
Lime	1530	1560
Lime and shale	1560	1960
Lime	1960	2060
Lime and shale	2060	2245
Lime	2245	2480
Lime and shale	2480	2580
Lime	2580	2615
Lime and shale	2615	2890
Shale	2890	2950
Lime and shale	2950	3090
Lime	3090	3409
Cherty Lime	3409	3412
Lime	3412	3530
Lime and shale	3530	3551
Lime	3551	3584 Total Depth

I, Don S. Packer, hereby certify that, to the best of my knowledge and belief, the above log is true and correct.

Subscribed and sworn to before me this 18th day of April, 1947.

[Signature]
 MAY 21 1947
Mary R. Brown
 Notary Public

My commission expires: *Dec 23, 1950*

PLUGGING
 FILE SEC 13 9 R 19W
 BOOK PAGE 110 LINE 33

HARBAR DRILLING COMPANY

WICHITA 2, KANSAS

May 20, 1947

State Corporation Commission
Bitting Building
Wichita, Kansas

Gentlemen:

Enclosed, herewith, is Drilling Log,
Well Plugging Record and Well Plugging Application on
the Hilgers #1, located in the NE $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$ of Sec. 13-9S-19W,
Rooks County, Kansas.

Yours very truly,

HARBAR DRILLING COMPANY

By *Helen Kelly*

HK/s

Encls.

