

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 13 Twp. 9 Rge. 19W (E) (W)
SW

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Eli Boisvert
Lease Name Boisvert Well No. 4
Office Address c/o W.E. Wickizer, Wakeeney, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 12, 1953 19
Application for plugging filed Aug. 10, 1953 19
Application for plugging approved Aug. 21, 1953 19
Plugging commenced Oct. 2, 1953 19
Plugging completed Oct. 7, 1953 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3571 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2	3532	2825
				8 5/8	167	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" at 170' circulated with cement - 5 1/2" at 3570' with 100 sax cement behind, Perforated at 3305' squeezed off perforations with cement.
Sand to 3560', set 4 sax cement with dump bailer, pulled 2825' 5 1/2", filled with mud to 170', set rock and 15 sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Co.
Address Great Bend, Kansas

STATE OF _____, COUNTY OF _____, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Wickizer
Wakeeney (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1953
Joy B. Korak Notary Public.

My commission expires Sept. 10, 1955

PLUGGING
FILE SEC 13 T 9 R 19W
BOOK PAGE 183 LINE 23

RECEIVED
NOV 17 1953
11-19-53
CONSERVATION DIVISION
Wichita, Kansas

GOLDEN CAT DRILLING and SERVICING COMPANY

Office Phone 379

Residence Phone 350

AUG 26

P. O. Box 611

To _____

Well Boisvert ^{NWC} SW-SW Sec. 13 Tw. 9 R. 19 Co. Rooks Co Ks.

Set 8 5/8 casing @ 167 ft

- 167 - 235 Shale
- 235 - 550 Shale & Shells
- 550 - 940 Shale & Sand
- 940 - 1240 Shale & Sand
- 1240 - 1360 Red Bed
- 1360 - 1390 Red Bed
- 1390 - 1476 Shale & Sand
- 1476 - 1514 Anhydrite
- 1514 - 1730 Shale & Shells
- 1730 - 1930 Shale
- 1930 - 2065 Shale & Shells
- 2065 - 2255 Salt Shale & Shells
- 2255 - 2580 Lime & Shale
- 2580 - 2640 Shale & Lime
- 2640 - 2790 Lime & Shale
- 2790 - 2900 Shale & Lime
- 2900 - 3110 Lime & Shale
- 3110 - 3210 Lime
- 3210 - 3250 Lime & Shale
- 3250 - 3350 Lime
- 3340 - 3450 Lime
- 3450 - 3485 Broken Lime
- 3485 - 3532 Lime
- 3532 - 3559 T.D.

Com. Well April 27 1953

Completed May 12 1953

RECEIVED
STATE CONSERVATION COMMISSION

Elevation 2102 R.R.

KG 3285 - 1183

Arb 3529 - 1427

Set 5 1/2 Casing 3532 ran Temp Survey cement up to 2885

AUG 26 1953
8-26-53
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
PTK SEC 13 T 9 R 19
BOOK PAGE 123 LINE 23

W. E. Heukiger