

15-163-21109-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rooks SEC. 11 TWP. 9s RGE. 20 ~~E/W~~  
 Location as in quarters or footage from lines:  
SW SE NE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Thomason Oil Company  
 Lease Name Allan R Well No. 1  
 Office Address 2700 Oak St., Suite A  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed 8-7-80  
 Application for plugging filed 9-2-83  
 Plugging commenced 10-14-83 @ 12:00 PM  
 Plugging completed 10-14-83 @ 12:45 PM  
 Reason for abandonment of well or producing formation Packer  
hung up in well

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation Tor & L/KC Depth to top 3284 bottom 3584 T.D. 3637

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Topeka-Plattmouth</u>	<u>Lime</u>	<u>3284</u>	<u>3287</u>	<u>8 5/8</u>	<u>210</u>	<u>None</u>
<u>Toronto</u>	<u>Lime</u>	<u>3337</u>	<u>3340</u>	<u>5 1/2</u>	<u>3637</u>	<u>None</u>
<u>L/KC</u>	<u>Lime</u>	<u>3355</u>	<u>3357</u>			
<u>L/KC</u>	<u>Lime</u>	<u>3510</u>	<u>3513</u>			
<u>L/KC</u>	<u>Lime</u>	<u>3529</u>	<u>3534</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_  
 feet to \_\_\_\_\_ feet for each plug set. Allied Cementing pumped 100 sxs of 50/50 Pos 6% gel  
3% cc. Between 8 5/8" surface pipe and 5 1/2" csg. Then pumped 300 sxs of 50/50 Pos 6%  
gel 3% cc down 5 1/2" csg; 6 sxs hulls. PSI on csg 400#. PSI on backside 400#

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing

STATE OF Kansas COUNTY OF Rooks, ss.

Steven Thomason (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Steven Thomason  
2520 Marjorie Drive  
Hays, Ks (Address) 67601

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 83

NOTARY PUBLIC - State of Kansas  
 Roxie VonLintel  
 My Appt. Exp. \_\_\_\_\_

My Commission expires:

Roxie VonLintel  
 Notary Public.

RECEIVED  
 CORPORATION COMMISSION  
 10/17/83  
 OCT 17 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas

# L-K Wireline

## R / A LOG

FILING NO. \_\_\_\_\_

COMPANY C.C. & S. OIL OPERATIONS

WELL ALLEN #1 "R"

FIELD \_\_\_\_\_

COUNTY ROOKS STATE KANSAS

LOCATION: \_\_\_\_\_

SW - SE - NE

SEC 11 TWP 9S RGE 20W

OTHER SERVICES  
BOTTOM  
GAMMA  
RAY

PERMANENT DATUM GROUND LEVEL ELEV. 2118 K.B. 2123

LOG MEASURED FROM KELLY BUSHING 5 FT. ABOVE PREM. DATUM D.F. 2120

DRILLING MEASURED FROM KELLY BUSHING O.I. 2118

DATE	9-15-30	9-15-80
RUN NO.	ONE	ONE
TYPE LOG	GAMMA RAY	NEUTRON
DEPTH-DRILLER		
DEPTH-LOGGER	3641	3641
BOTTOM LOGGED INTERVAL	3640	3640
TOP LOGGED INTERVAL	3050	3050
TYPE FLUID IN HOLE	WATER	
SALINITY, PPM CL		
DENSITY		
LEVEL	2200	
MAX. REC. TEMP. DEG. F.		
OPERATING RIG TIME	ONE HOUR	
RECORDED BY	RANDY K. LONGPINE	
WITNESSED BY		

RUN NO.	BORE-HOLE RECORD			CASING RECORD			
	BIT	FROM	TO	SIZE	WGT.	FROM	TO
ONE	12-1/4	SURFACE	210	8-5/8		SURFACE	210
TWO	7-7/8	210	3638	5-1/2		SURFACE	3637

