

RECEIVED

KANSAS CORPORATION COMMISSION

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

4/4/02  
APR 04 2002

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-02249-00-00

LEASE NAME Copeland

WELL NUMBER #5

2310 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 19 TWP. 9S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed

Plugging Commenced 4/2/02

Plugging Completed 4/2/02

CONSERVATION DIVISION  
WICHITA, KS

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Great Eastern Energy & Development Corp.

ADDRESS P. O. Box 150 Bogue, KS 67625

PHONE 785 623-7520 OPERATORS LICENSE NO. 9449

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 13, 2002 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Arbuckle Depth to Top 3826 Bottom 3831 T.O. 3831

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	0	249	10"	249	0
		0	3825	7"	3822	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Tubing to 3650' Spot 42sx gel Followed w/ 50sx cement w/ 300# hull pull to 2350'  
Spot 125sx cement w/ 100# hull pull to 1100' spot 7sx gel follow w/ 50sx cement w/ 100# hulls pull to 300' circ cement w/ 40 sx cement Pump down casing w/ 65 sx 500psi shut in pump back side w/ 10sx

Name of Plugging Contractor Allied Cementing License No. N/A

Address P. O. 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Eastern Energy & Development Corp.

STATE OF Texas COUNTY OF Midland, ss.

Great Eastern Energy & Development Corp.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]


(Address) P. O. Drawer 2436 Midland, TX 79701

SUBSCRIBED AND SWORN TO before me this 3 day of April, 2002

[Signature]

Notary Public

My Commission Expires: 1-20-11



OK