

15-163-30048-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 8-3-65
LEASE NAME J. L. Balthazor
WELL NUMBER 5
 Ft. from S Section Line
C E 1/2 NW NE Ft. from E Section Line
SEC. 19 TWP. 9 RGE. 20 (E) or (W)
COUNTY Rooks
Date Well Completed 8-3-65
Plugging Commenced 1-20-93
Plugging Completed 1-20-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corp.
ADDRESS Box 723 Hays, Kansas 67601
PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5364
Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-20-93 (date)
by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D 3806

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	230	8 5/8		none
	Casing	0	3800	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Run tubing to 3693'. Spot 75 sk. 65/35 pos. 8% gel, 2 sk. hulls. Pull tubing to 2703'. Spot 75 sk. 65/35 pos. 8% gel, 2 sk. hulls. Pull tubing to 1673'. Circulate cement to surface 65/35 pos. 8% gel, 110 sk. 1/2 sk. hulls. Hook to 8 5/8 120 sk. 65/35 pos. 8% gel, Max. 100# Shut in 50#. Hook to 5 1/2 pump 20 sk. 65/35 pos. 8% gel, Max. 500# SHUT in 200#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berexco, Inc. License No. 5363
Address Box 723 Hays, Kansas 67601

RECEIVED
STATE CORPORATION COMMISSION
2/2/93
1993
CONSOLIDATION DIVISION
WICHITA, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corp.
STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
ROSEMARY SMITH
My Appt. Exp. 5-1-1995
SUBSCRIBED AND SWORN TO

(Signature) Ted Crawford
(Address) Box 723 Hays, Mo 67601
29 day of January, 19 93
Rosemary Smith
Notary Public

My Commission Expires: 5-1-1995