

15-163-30444-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 26 Twp. 9S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Lee Phillips Oil Company

Lease Name Steeples Well No. 1

Office Address Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-23 1952

Application for plugging filed 11-23 1952

Application for plugging approved 11-23 1952

Plugging commenced 11-23 1952

Plugging completed 11-23 1952

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3767 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 240' with 15 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
12/3/52
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Anschutz Drilling Company, Inc.

Address Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler

Union Nat'l Bk Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 1st day of December, 1952

My commission expires May 2, 1956

Notary Public.

PLUGGING
FILE SEC 26 T 9 R 20
BOOK PAGE 12 LINE 29

DRILLER'S LOG

Lee Phillips Oil Company
 #1 Steeples
 SE SE NE - 26-9S-20W
 Rooks County, Kansas

<u>FROM</u>	<u>TO</u>	
0	60	Clay, sand & shale
60	257	Shale & shells
257	480	Shale
480	890	Shale & sand streaks
890	1020	Sand
1020	1065	Shale
1065	1165	Sand, shale & shells
1165	1370	Sand
1370	1490	Red bed
1490	1643	Shale & red bed
1643	1688	Anhydrite
1688	2355	Shale & shells
2355	2450	Shale & lime
2450	2610	Shale & shells
2610	2935	Lime & shale
2935	3050	Lime
3050	3455	Lime & shale
3455	3642	Lime
3642	3687	Lime & shale
3687	3727	Lime, chert & shale
3727	3748	Lime & shale
3748	3767	Lime
	3767	TOTAL DEPTH
		D&A

COMMENCED: 11-12-52
 COMPLETED: 11-23-52

CASING RECORD

Set 8-5/8" surface casing at
 252' with 150 sacks cement.

ELEVATION: 2206 KB

TOPS

Topeka 3242
 Heebner 3410
 Toronto 3430
 Lansing 3451
 Base Kansas City 3664
 Conglomerate 3695
 Arbuckle 3647

DRILL STEM TEST'S

3517-3539, open 20 minutes, re-
 covered 630' salt
 water, BHP 1340#.
 3594-3605, open 20 minutes, re-
 covered 4' mud, BHP 0#

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Steeples well, located SE SE NE of Section 26-9S-20W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

RECORDED
 STATE CORPORATION DIVISION

DEC - 3 1952

BY:

Leon L. Mehler
 Leon L. Mehler

CONSERVATION DIVISION

Wichita, Kansas

Subscribed and sworn to before me this 1st day of December, 1952.

Jaqueline Kinnon
 Notary Public

My Commission Expires: May 2, 1956

PLUGGING
 FILE SEC 26 T 9 S 20 W
 BOOK PAGE 62 LINE 29